

**HS RESOURCES, INC.**

**HSR-Smythe 14-27X**

**LOCATION:** SE/SW Sec 27-T3N-R66W 6th P.M.

**FIELD:** Wattenberg

**COUNTY:** Weld

**STATE:** CO

**API#:** 05-123-14181-2

**Surface location:** 660' FSL & 1980' FWL

**GL Elevation:** 4954'

**KB Elevation:** 4965'

**Spud date:** 06/20/97

**TD date:** 06/23/97

**Bottom hole location:** 455' FSL & 2140' FWL

**ZONES PRODUCING** **Codell**



TOC 6885'

**Codell 7460' - 7464'**

FRAC DATA:		
10020 # 100 mesh	Codell	Frac Date: 07/18/97
247500 # 20/40 mesh		
20,000 # 12/20 mesh		
106302 gal. gelled fluid		

Elaine Rivas  
10/8/97

Not To Scale

**LINER**  
2-7/8" 6.5#  
set @ 7574'  
25 sacks cement

TD @ 7574'  
HSR-Smythe 14-27X

TD @ 7535'  
HSR-Smythe 14-27

12-1/4" HOLE

**SURFACE CSG**

8-5/8 24#

set 582'

350 sacks cement

7-7/8" HOLE

TOC 6310'

2-3/8" TUBING  
SET @ 6676'

CIBP 6794'

Niobrara 7129' - 7189'

FRAC DATA:		
230100 # 20/40 mesh	Niobrara	Frac Date: 07/26/93
64360 gal. gelled fluid		

Codell 7394' - 7411'

FRAC DATA:		
24000 # 100 mesh	Codell	Frac Date: 01/17/90
500000 # 16/30 mesh		
88050 gal. gelled fluid		

**PRODUCTION CSG**  
4-1/2" 11.6#  
set @ 7528'  
230 sacks cement