

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400271323

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

20080034

3. Name of Operator: BAYSWATER EXPLORATION AND PRODUCTION LLC

4. COGCC Operator Number: 10261

5. Address: 730 17TH ST STE 610

City: DENVER State: CO Zip: 80202

6. Contact Name: Kristi McRedmond Phone: (303)928-7128 Fax: (303)962-6237

Email: kristi@petro-fs.com

7. Well Name: MOJACK Well Number: 24-28

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7410

WELL LOCATION INFORMATION

10. QtrQtr: SWNE Sec: 28 Twp: 7N Rng: 64W Meridian: 6

Latitude: 40.547277 Longitude: -104.550365

Footage at Surface: 1478 feet FNL/FSL FNL 1392 feet FEL/FWL FEL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4895 13. County: WELD

14. GPS Data:

Date of Measurement: 03/01/2012 PDOP Reading: 2.1 Instrument Operator's Name: Shawn Lee/PFS

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2568 FNL 1333 FEL 2638 FNL 1319 FEL
Sec: 28 Twp: 7N Rng: 64W Sec: 28 Twp: 7N Rng: 64W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1142 ft

18. Distance to nearest property line: 75 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 974 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL	unspaced		S/2NE/4
Niobrara	NBRR	unspaced		S/2NE/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

NE/4 Section 28, Township 7N Range 64W

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	740	518	740	0
1ST	7+7/8	4+1/2	11.6	0	7,410	849	7,410	3,450

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments No conductor pipe will be set.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kristi L McRedmond

Title: Regulatory Technician Date: _____ Email: kristi@petro-fs.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400271345	PLAT
400271346	TOPO MAP
400274857	DEVIATED DRILLING PLAN
400281194	DIRECTIONAL DATA
400281195	30 DAY NOTICE LETTER

Total Attach: 5 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Construction	Remove only the minimum amount of vegetation necessary for the construction of roads and facilities. Conserve topsoil during excavation and reuse as cover on disturbed areas to facilitate regrowth of vegetation. No construction or routine maintenance activities will be performed during periods when the soil is too wet to adequately support construction equipment.
Drilling/Completion Operations	When available and reasonable use a closed-loop drilling mud system to preclude the use of an earthen reserve pits when available.
Final Reclamation	All surface restoration shall be accomplished to the satisfaction of Owner. All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner. Final reclamation shall be completed to the reasonable satisfaction of the Owner as soon as practical after installation (weather permitting) and in accordance with regulatory agency standards (BLM/COGCC).
Interim Reclamation	Utilize only such area around each producing well as is reasonably necessary. Restore the remainder of the well site location to its original condition within a reasonable time after the completion of operations. All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner.
Planning	When feasible develop multiple well sites by using directional drilling to reduce cumulative impacts and adverse impacts on wildlife resources
Site Specific	Fence the well site after drilling to restrict public and wildlife access. Keep well site location, the road, and the pipeline easement free of noxious weeds, litter and debris. Spray for noxious weeds, and implement dust control, as needed. Bayswater Exploration and Production, LLC will not permit the release or discharge of any toxic or hazardous chemicals or wastes on Owner's Land. Construct and maintain gates where any roads used by Bayswater Exploration and Production, LLC, its employees, or contractors cross through fences on the leased premises.
Storm Water/Erosion Control	Use water bars, and other measures to prevent erosion and non-source pollution. Implement and maintain BMPs to control stormwater runoff in a manner that minimizes erosion, transport of sediment offsite, and site degradation. Co-locate gas and water gathering lines whenever feasible, and mitigate any erosion problems that arise due to the construction of any pipeline(s).

Total: 7 comment(s)