

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400271598

Date Received:

04/13/2012

PluggingBond SuretyID

20010124

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
 SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☐Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: Rebecca Heim Phone: (720)929-6361 Fax: (720)929-7361

Email: rebecca.heim@anadarko.com

7. Well Name: LAMBRECHT Well Number: 27-2

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 8268

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 2 Twp: 1N Rng: 67W Meridian: 6

Latitude: 40.085842 Longitude: -104.850464

Footage at Surface: 617 feet FNL/FSL 460 feet FEL/FWL
 FNL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4941 13. County: WELD

14. GPS Data:

Date of Measurement: 03/15/2012 PDOP Reading: 2.3 Instrument Operator's Name: SHAUN LEE

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
 50 FNL 1270 FEL 50 FNL 1270 FEL
 Sec: 2 Twp: 1N Rng: 67W Sec: 2 Twp: 1N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 460 ft

18. Distance to nearest property line: 460 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 889 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J SAND	JSND		160	GWA
NIOBRARA CODELL	NB-CD	407	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please see attached Oil and Gas Lease.

25. Distance to Nearest Mineral Lease Line: 50 ft

26. Total Acres in Lease: 190

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24.0	0	915	641	915	0
1ST	7+7/8	4+1/2	11.6	0	8,268	200	8,268	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be used. Unit Configuration NB-CD 2:N/2NE/4; 35:S/2SE/4; JSND 2:N/2NE/4, 35:S/2SE/4

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Rebecca Heim

Title: Regulatory Analyst II

Date: 4/13/2012

Email: DJRegulatory@anadarko.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____

Director of COGCC

Date: 5/10/2012

API NUMBER

05 123 35581 00

Permit Number: _____

Expiration Date: 5/9/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU..
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
400271598	FORM 2 SUBMITTED
400271604	EXCEPTION LOC REQUEST
400271605	EXCEPTION LOC WAIVERS
400271609	OTHER
400272051	DIRECTIONAL DATA
400272052	30 DAY NOTICE LETTER
400272053	DEVIATED DRILLING PLAN
400272056	PROPOSED SPACING UNIT
400272057	PLAT
400272559	OIL & GAS LEASE
400272560	TOPO MAP

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed. No LGD or public comment received.	5/8/2012 9:44:41 AM
Permit	change to "the distance to nearest well" from 1617' to 889' per operator. ok to pass.	4/24/2012 11:39:35 AM
Permit	Operator requests approval of a Rule 318Aa and Rule 318Ac exception location: Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location. Request and waivers attached.	4/24/2012 9:47:28 AM
Permit	Reviewed and Approved Operator's request for omission of open hole logs.	4/24/2012 9:47:08 AM
Permit	requesting change to "the distance to nearest well" from 1617' to 889'.	4/24/2012 9:44:43 AM
Permit	Operator corrected topo attachment. This form has passed completeness.	4/16/2012 12:03:53 PM
Permit	Returned to draft. Topo attachment will not open.	4/16/2012 8:54:30 AM

Total: 7 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)