

FORM  
5Rev  
02/08

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400283711

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100185

4. Contact Name: Marina Ayala

2. Name of Operator: ENCANA OIL &amp; GAS (USA) INC

Phone: (720) 876-5905

3. Address: 370 17TH ST STE 1700

Fax: (720) 876-6905

City: DENVER State: CO Zip: 80202-

5. API Number 05-045-20671-00

6. County: GARFIELD

7. Well Name: Federal

Well Number: 25-5A (PE-25)

8. Location: QtrQtr: SWNW Section: 25 Township: 7S Range: 96W Meridian: 6

Footage at surface: Distance: 2043 feet Direction: FNL Distance: 18 feet Direction: FWL

As Drilled Latitude: 39.409862 As Drilled Longitude: -108.067365

## GPS Data:

Data of Measurement: 09/06/2011 PDOP Reading: 2.1 GPS Instrument Operator's Name: Brandon Birdsall

\*\* If directional footage at Top of Prod. Zone Dist.: 1353 feet. Direction: FNL Dist.: 821 feet. Direction: FWL  
Sec: 25 Twp: 7S Rng: 96W

\*\* If directional footage at Bottom Hole Dist.: 1303 feet. Direction: FNL Dist.: 847 feet. Direction: FWL  
Sec: 25 Twp: 7S Rng: 96W

9. Field Name: PARACHUTE

10. Field Number: 67350

11. Federal, Indian or State Lease Number: COC27825

12. Spud Date: (when the 1st bit hit the dirt) 09/19/2011 13. Date TD: 10/23/2011 14. Date Casing Set or D&amp;A: 10/24/2011

## 15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 5980 TVD\*\* 5804 17 Plug Back Total Depth MD 5911 TVD\*\* 5735

18. Elevations GR 5396 KB 5418

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

RST, IBC and Mud.

## 20. Casing, Liner and Cement:

## CASING

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Top | Cmt Bot | Status |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|--------|
| CONDUCTOR   | 26           | 16             | 42    | 0             | 40            | 40        | 0       | 40      | CALC   |
| SURF        | 12+1/4       | 9+5/8          | 36    | 0             | 1,128         | 380       | 0       | 1,128   | CALC   |
| 1ST         | 8+3/4        | 4+1/2          | 11.6  | 0             | 5,955         | 652       | 2,190   | 5,980   | CBL    |

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

| Method used | String | Cementing tool setting/pref depth | Cement volume | Cement top | Cement bottom |
|-------------|--------|-----------------------------------|---------------|------------|---------------|
|             |        |                                   |               |            |               |

Details of work:

21. Formation log intervals and test zones:

**FORMATION LOG INTERVALS AND TEST ZONES**

| FORMATION NAME | Measured Depth |        | Check if applies         |                          | COMMENTS (All DST and Core Analyses must be submitted to COGCC) |
|----------------|----------------|--------|--------------------------|--------------------------|---|
|                | Top            | Bottom | DST                      | Cored                    |   |
| MESAVERDE      | 2,856          | 3,511  | <input type="checkbox"/> | <input type="checkbox"/> |   |
| WILLIAMS FORK  | 3,512          | 5,725  | <input type="checkbox"/> | <input type="checkbox"/> |   |
| ROLLINS        | 5,726          | 5,980  | <input type="checkbox"/> | <input type="checkbox"/> |   |

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Marina Ayala

Title: Permitting Technician

Date: \_\_\_\_\_

Email: marina.ayala@encana.com

**Attachment Check List**

| Att Doc Num                 | Document Name         | attached ? |                                     |    |                                     |
|-----------------------------|-----------------------|------------|-------------------------------------|----|-------------------------------------|
| <u>Attachment Checklist</u> |                       |            |                                     |    |                                     |
| 400283716                   | CMT Summary *         | Yes        | <input checked="" type="checkbox"/> | No | <input type="checkbox"/>            |
|                             | Core Analysis         | Yes        | <input type="checkbox"/>            | No | <input checked="" type="checkbox"/> |
| 400283714                   | Directional Survey ** | Yes        | <input checked="" type="checkbox"/> | No | <input type="checkbox"/>            |
|                             | DST Analysis          | Yes        | <input type="checkbox"/>            | No | <input checked="" type="checkbox"/> |
|                             | Logs                  | Yes        | <input checked="" type="checkbox"/> | No | <input type="checkbox"/>            |
|                             | Other                 | Yes        | <input type="checkbox"/>            | No | <input checked="" type="checkbox"/> |
| <u>Other Attachments</u>    |                       |            |                                     |    |                                     |
| 400283715                   | DIRECTIONAL DATA      | Yes        | <input checked="" type="checkbox"/> | No | <input type="checkbox"/>            |
| 400283718                   | PDF-MUD               | Yes        | <input checked="" type="checkbox"/> | No | <input type="checkbox"/>            |
| 400283721                   | LAS-CEMENT BOND       | Yes        | <input checked="" type="checkbox"/> | No | <input type="checkbox"/>            |
| 400283723                   | LAS-NEUTRON           | Yes        | <input checked="" type="checkbox"/> | No | <input type="checkbox"/>            |

**General Comments****User Group****Comment****Comment Date**

|  |  |  |
|--|--|--|
|  |  |  |
|--|--|--|

Total: 0 comment(s)