

FORM
5

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400284765

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

1. OGCC Operator Number: 8960 4. Contact Name: Bryan Brown
2. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY Phone: (720) 440-6100
3. Address: P O BOX 21974 Fax: (720) 279-2331
City: BAKERSFIELD State: CA Zip: 93390

5. API Number 05-123-35126-00 6. County: WELD
7. Well Name: Antelope Well Number: P-19
8. Location: QtrQtr: SENE Section: 19 Township: 5N Range: 62W Meridian: 6
Footage at surface: Distance: 1954 feet Direction: FNL Distance: 684 feet Direction: FEL
As Drilled Latitude: 40.386800 As Drilled Longitude: -104.359110

GPS Data:

Date of Measurement: 04/26/2012 PDOP Reading: 2.1 GPS Instrument Operator's Name: Adam Kelly

** If directional footage at Top of Prod. Zone Dist.: 63 feet. Direction: FNL Dist.: 1277 feet. Direction: FEL
Sec: 19 Twp: 5n Rng: 62w

** If directional footage at Bottom Hole Dist.: 63 feet. Direction: FNL Dist.: 1277 feet. Direction: FEL
Sec: 19 Twp: 5n Rng: 62w

9. Field Name: WATTENBERG 10. Field Number: 90750
11. Federal, Indian or State Lease Number: _____

12. Spud Date: (when the 1st bit hit the dirt) 03/26/2012 13. Date TD: 03/30/2012 14. Date Casing Set or D&A: 03/31/2012

15. Well Classification:

Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

16. Total Depth MD 7120 TVD** 6714 17 Plug Back Total Depth MD 7107 TVD** 6701

18. Elevations GR 4652 KB 4662

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, GAMMA RAY, HRI, CDL, CNL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	462	330	0	462	CALC
1ST	7+7/8	4+1/2	11.6	0	7,107	460	3,034	7,120	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHARON SPRINGS	6,576		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6,686		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	6,920		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	6,946		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: BRYAN BROWN

Title: DRILLING EIT Date: _____ Email: bbrown@bonanza.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400284790	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400284787	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400284781	LAS-TRIPLE COMBINATION	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400284784	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400284785	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400284786	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)