



**CEMENTER'S WELL SERVICE, INC.**  
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

**200308**

Date <b>3/27/2012</b>	Well Owner <b>BONANZA CREEK</b>	Well No. <b>P-19</b>	Lease <b>ANTELOPE</b>
County <b>WELD</b>	State <b>COLORADO</b>	Field	
Charge to <b>BONANZA CREEK OPERATING</b>			Charge Code
Address <b>410 17TH STREET STE #1500 (MID-CON#1)</b>			For Office Use Only
City, State <b>DENVER, COLORADO 80202</b>			
Pump Truck No. <b>1201</b>	Code	Bulk Truck No. <b>1214</b>	Code
Type of Job		Depth	Ft. <b>487</b>
Surface <b>8 5/8" CSG-24"</b>		Bottom of Surface	Ft. <b>472</b>
Plug		Plug Landed @ <b>441</b>	Ft. Time On <b>0245</b>
Production		Pipe Landed @ <b>472</b>	Ft. Time Off <b>0430</b>

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat ✓	330	SKS		
	Poz. Mix				
	Calcium Chloride	390			
	Gel % Flo-Cele 1/4# Per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement				
8 5/8"	GUIDE SHOE	1			
"	CEMENT BASKET	1			
1"	CENTRALIZERS	3			
1"	BAFFLE PLATE	1			
	BOX THREAD LOCK	1			
	MIXING RATE 4 BPM / DISP RATE 5 BPM				
	SLURRY VOL 1.18 CU FT / SK-SLURRY WT 14.8-15.0 PPG				
	TOTAL SLURRY VOL 69.3 BBL CEMENT / PLUG LANDED @ 650 PSI				

Remarks: <b>PRE-FLUSH W/10 BBLs H<sub>2</sub>O</b>	Tax Reference Code	Sub Total
<b>DISPLACE W/28 BBLs H<sub>2</sub>O</b>	State <b>CO 2.9 %</b>	Tax
<b>CIRCULATE 6 BBLs CEMENT</b>	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		25	1835 28		
1214		Bulk Truck		25	CO 007/86		
					8305 205		

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JIM ADAM / JASON WELLS**

Received By **APPROVED FOR PAYMENT**  
**Hudson**  
Customer or His Agent