



CEMENTER'S WELL SERVICE, INC.
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600206

Date	11/20/2012	Well Owner	Kerr McGee	Well No.	36n-11H7	Lease	Cannon
County		State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME#8)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	950		
Surface	9 5/8" CSG 3 1/2" 13 1/2" Hole	Bottom of Surface		Ft.	942		
Plug		Plug Landed @	899	Ft.	Time On	1130	
Production		Pipe Landed @	942	Ft.	Plug Down	1645	

Description	Qty.	Meas.
Set Up Charge	1	
Cement Neat TYPE III	700	SKS
Poz. Mix User ID ZMDL6		
Calcium Chloride WBSAWO/CC 2059719.PRL	2.5	%
Gel % Fio-Cete 1/4 # Per Sack		
Mileage Charge G/L Acct. \$0012090	156	Miles
Fuel Surcharge	156	MILES
Additional Cement		SKS
Mixing Rate 4 BPM	Pre-Flush 1541	1547
Disp. Rate 5 BPM	Mixing 1547	1629
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves 1629	1631
Slurry Wt. 14.8 - 15.0 PPG	Displacement 1631	1645
Water/Cement 6.25 Gal/SK		WBSAWO
Water Temp. 62		
Total Slurry Vol. 164.5	BBLS Cement	G/L Acct.
Landed Plug @ 850	PSI/Final Lift @ 325	PSI
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code
Displace W/ 69.5	BBLS H ₂ O	State CO 2.9%
Circulate 7	BBLS Cement	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		52			
1234/1216		Bulk Truck		52/52			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim Adam/Jason

Received By Jim Adam

Customer or His Agent