



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600198

Date	11/21/2011	Well Owner	Kerr McGee	Well No.	28C-25HZ	Lease	CAMP
County		State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAJOR #44)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	884		
Surface	9 5/8 CSA 36" 12 1/4 HOLE	Bottom of Surface		Fl.	873		
Plug		Plug Landed @	830	Fl.		Time On	057
Production		Pipe Landed @	873	Fl.		Plug Down	0530

Description	Qty.	Meas.
Set Up Charge	1	
Cement Neat TYPE III	420	SKS
Poz. Mix		
Calcium Chloride	2.5	%
Gel % Flo-Cete 4 # Per Sack	2059.553 DEL	
Mileage Charge	132	Miles
Fuel Surcharge	132	MILES
Additional Cement		SKS
Mixing Rate	4 BPM	Pre-Flush
Disp. Rate	5 BPM	Mixing
Slurry Vol.	1.32 Cu. Ft./Sk	Change Valves
Slurry Wt.	14.8 - 15.0 PPG	Displacement
Water/Cement	6.25 Gal/SK	
Water Temp.	46	
Total Slurry Vol.	98.7	BBLS Cement
Landed Plug @	400	PSI/Final Lift @ 180 PSI
Pre-Flush W/	20	BBLS H ₂ O
Displace W/	64.1	BBLS H ₂ O
Circulate	5	BBLS Cement

Tax Reference Code	Sub Total
State CO 2.9%	Tax
	Total