

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400261392

Date Received:

04/19/2012

PluggingBond SuretyID

20100017

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐3. Name of Operator: ENCANA OIL & GAS (USA) INC4. COGCC Operator Number: 1001855. Address: 370 17TH ST STE 1700City: DENVER State: CO Zip: 80202-56326. Contact Name: Erin Hochstetler Phone: (720)876-5827 Fax: ()Email: erin.hochstetler@encana.com7. Well Name: CB Well Number: DHS7B-32K2961008. Unit Name (if appl): MUD SPRING Unit Number: COC 75452X9. Proposed Total Measured Depth: 14251

## WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 29 Twp: 6S Rng: 100W Meridian: 6Latitude: 39.503467 Longitude: -108.578306

Footage at Surface: 2171 feet FNL/FSL FSL 2352 feet FEL/FWL FWL

11. Field Name: Wildcat Field Number: 9999912. Ground Elevation: 7033.9 13. County: GARFIELD

## 14. GPS Data:

Date of Measurement: 01/25/2012 PDOP Reading: 1.8 Instrument Operator's Name: Ben Johnson15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1960 FSL 696 FWL 666 FEL/FWL 625 FWL 666  
 Bottom Hole: FNL/FSL 666 FSL 625 FWL 666  
 Sec: 29 Twp: 6S Rng: 100 W Sec: 32 Twp: 6S Rng: 100 W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 6824 ft18. Distance to nearest property line: 275 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1369 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| Mancos                 | MNCS           |                         |                               |                                      |

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: \_\_\_\_\_22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T6S-R100W-Sec. 32: Tract 51 and other lands - end of BHL. other leases - COC 10374 - T6S-R100W-Sec. 29 - N/2SW/4 and Lots 7 and 8

25. Distance to Nearest Mineral Lease Line: 625 ft

26. Total Acres in Lease: 1134

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: RECYCLE AND BURY

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Wt/Ft     | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|-----------|---------------|---------------|-----------|---------|---------|
| CONDUCTOR   | 30           | 20             | line pipe | 0             | 120           | 319       | 120     | 0       |
| SURF        | 14+3/4       | 10+3/4         | 40.5      | 0             | 1,000         | 466       | 1,000   | 0       |
| 1ST         | 9+7/8        | 7+5/8          | 26.4      | 0             | 5,900         | 561       | 5,900   | 0       |
| 2ND         | 6+3/4        | 4+1/2          | 11.6      | 0             | 14,251        | 745       | 14,251  | 0       |

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments QUESTION 17 REFERS TO NEAREST PUBLIC ROAD. The 2nd string casing size will be 4 1/2 or 5 1/2 tapered string, weighing 11.6 and 17 respectively.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Erin Hochstetler

Title: Permitting Technician

Date: 4/19/2012

Email: erin.hochstetler@encana.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 5/18/2012

API NUMBER

05 045 21495 00

Permit Number: \_\_\_\_\_ Expiration Date: 5/17/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.
- 2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE
- 3) PROVIDE CEMENT COVERAGE FROM THE INTERMEDIATE CASING SHOE TO A MINIMUM OF 200' ABOVE TOP OF GAS [OR OTHER SHALLOWEST-KNOWN PRODUCING HORIZON]. VERIFY CEMENT WITH A CEMENT BOND LOG.
- 4) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

### **Attachment Check List**

| Att Doc Num | Name                   |
|-------------|------------------------|
| 1533101     | OTHER                  |
| 1533102     | UNIT CONFIGURATION MAP |
| 400261392   | FORM 2 SUBMITTED       |
| 400264948   | WELL LOCATION PLAT     |
| 400264949   | DEVIATED DRILLING PLAN |
| 400264950   | DIRECTIONAL DATA       |

Total Attach: 6 Files

### **General Comments**

| <b><u>User Group</u></b> | <b><u>Comment</u></b>  | <b><u>Comment Date</u></b> |
|--------------------------|--|----------------------------|
| Permit                   | off hold--confirmed new unit designation, Mud Spring Unit, with BLM and attached unit configuration map. This location is more than 600' from unit boundary. LGD passed; pub. comments waived. Final Review--passed. | 5/17/2012<br>9:32:36 AM    |
| Permit                   | on hold pending receipt of new proposed fed. unit boundary.  | 5/16/2012<br>2:50:32 PM    |
| LGD                      | Passed DB  | 5/14/2012<br>4:01:45 PM    |
| Permit                   | Operator changed #22. This form has passed completeness.   | 4/24/2012<br>2:55:57 PM    |
| Permit                   | Returned to draft. Missing SUA/ROW.  | 4/19/2012<br>2:15:10 PM    |

Total: 5 comment(s)

### **BMP**

| <b><u>Type</u></b> | <b><u>Comment</u></b> |
|--------------------|-----------------------|
|                    |                       |

Total: 0 comment(s)