

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400268199

Date Received:

04/11/2012

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

3. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

4. COGCC Operator Number: 96850

5. Address: 1001 17TH STREET - SUITE #1200

City: DENVER State: CO Zip: 80202

6. Contact Name: Howard Harris Phone: (303)606-4086 Fax: (303)629-8268

Email: howard.harris@williams.com

7. Well Name: Federal Well Number: RGU 34-36-198

8. Unit Name (if appl): Ryan Gulch Unit Unit Number: COC68239X

9. Proposed Total Measured Depth: 12402

WELL LOCATION INFORMATION

10. QtrQtr: Lot 10 Sec: 36 Twp: 1S Rng: 98W Meridian: 6

Latitude: 39.916133 Longitude: -108.339832

Footage at Surface: 1332 feet FNL/FSL FSL 1897 feet FEL/FWL FEL

11. Field Name: Sulphur Creek Field Number: 80090

12. Ground Elevation: 6579 13. County: RIO BLANCO

14. GPS Data:

Date of Measurement: 10/14/2011 PDOP Reading: 1.8 Instrument Operator's Name: J. Kirkpatrick

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1018 FSL 1911 FEL FEL Bottom Hole: FNL/FSL 1018 FSL 1911 FEL FEL  
Sec: 36 Twp: 1S Rng: 98W Sec: 36 Twp: 1S Rng: 98W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 250 ft

18. Distance to nearest property line: 5994 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 719 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES			
Sego	SEGO			
Williams Fork	WMFK			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC60735

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

☒

23. Is the Surface Owner also the Mineral Owner? Yes ☐ No ☐ Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See Attached

25. Distance to Nearest Mineral Lease Line: 627 26. Total Acres in Lease: 1209

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-Use, Evap & Backfill

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	30	18	48	0	80	100	80	0
SURF	14+3/4	9+5/8	36	0	3,629	1,454	3,629	0
1ST	8+3/4	4+1/2	11.6	0	12,402	1,175	12,402	7,272

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Top of production casing will be approx 200 feet above the top of Mesaverde. Fed minerals and Fed surface. We are permitting 8 wells at this time to be drilled from this pad. Closed loop mud system will be used. See Williams WPX Energy Master 10 point Drilling Plan dated 3/24/11 for all specific drilling stipulations.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Howard Harris

Title: Sr. Regulatory Specialist Date: 4/11/2012 Email: howard.harris@williams.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 5/18/2012

#### API NUMBER

05 103 11929 00

Permit Number: \_\_\_\_\_ Expiration Date: 5/17/2014

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name
400268199	FORM 2 SUBMITTED
400271069	DIRECTIONAL DATA
400271078	FED. DRILLING PERMIT
400271082	LEGAL/LEASE DESCRIPTION
400271085	DEVIATED DRILLING PLAN
400271093	WELL LOCATION PLAT

Total Attach: 6 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	LGD/pub. comments waived. Location in fed. unit; meets setback requirements. Final Review--passed.	5/14/2012 8:17:55 AM

Total: 1 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)