

T27S, R69W, 6th P.M.

SWEPI LP

Set Marked Stone,  
0.6' High  
Lat: 37.693639°  
Long: 105.069300°

S89°19'15"E - 2590.94' (Meas.)

S89°39'E - 2651.22' (G.L.O.)

Set Marked Stone,  
Private Alum. Cap,  
0.6' High  
Lat: 37.693544°  
Long: 105.060350°

R 69  
W 68  
R

N0°50'55"E - 5337.01' (Meas.)

NORTH - 5280.00' (G.L.O.)

NOTE:  
SEE ADDENDUM TO LEGAL PLAT FOR  
EXISTING IMPROVEMENTS WITHIN 400'  
OF THE PROPOSED WELL DISTURBANCE.

24

FREEMAN #3-24

Elev. Ungraded Ground = 7070'

536'

2105'

N87°51'02"E - 5297.78' (Meas.)

1996 Private Alum.  
Cap, 0.2' High  
Lat: 37.678992°  
Long: 105.069603°

Private Alum. Cap,  
Flush W/Ground  
Lat: 37.679511°  
Long: 105.051317°

LEGEND:

— = 90° SYMBOL

● = PROPOSED WELL HEAD.

▲ = SECTION CORNERS LOCATED.

PDOP = 2.0

NAD 83 (SURFACE LOCATION)

LATITUDE = 37°41'05.39" (37.684831)

LONGITUDE = 105°04'03.47" (105.067631)

NAD 27 (SURFACE LOCATION)

LATITUDE = 37°41'05.36" (37.684822)

LONGITUDE = 105°04'01.48" (105.067078)

Well location, FREEMAN #3-24, located as shown in the NW 1/4 SW 1/4 of Section 24, T27S, R69W, 6th P.M., Huerfano County, Colorado.

BASIS OF ELEVATION

SPOT ELEVATION IN THE NORTHEAST 1/4 OF SECTION 33, T26S, R70W, 6th P.M., TAKEN FROM THE LITTLE SHEEP MOUNTAIN QUADRANGLE, COLORADO, 7.5 MINUTE QUAD (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 7455 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



1000' 0' 500' 1000'

S C A L E

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED, FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

ERT L  
OS 15  
ER, MY  
AND CORRECT  
TO THE  
OF 03-29-12

REGISTERED LAND SURVEYOR  
REGISTRATION NO. 17492  
STATE OF COLORADO

REV.: 03-29-12

REV.: 02-08-12

UNTAH ENGINEERING & LAND SURVEYING

85 SOUTH 200 EAST - VERNAL, UTAH 84078

(435) 789-1017


SCALE 1" = 1000' DATE SURVEYED: 01-17-12 DATE DRAWN: 01-23-12

PARTY J.H. C.M. J.I. REFERENCES G.L.O. PLAT

WEATHER COOL FILE

SWEPI LP

SWEPI LP  
ADDENDUM TO LEGAL PLAT FOR  
FREEMAN #3-24  
SECTION 24, T27S, R69W, 6th P.M.  
2105' FSL 536' FWL



SCALE: 1" = 200'  
DATE: 01-23-12  
DRAWN BY: J.I.  
REV.: 02-08-12

