



**CEMENTER'S WELL SERVICE, INC.**  
P.O. BOX 338220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

**600441**

Date <b>4/5/2012</b>	Well Owner <b>Kerr McGee</b>	Well No. <b>6-1</b>	Lease <b>HEIN</b>
County <b>WELD</b>	State <b>Colorado</b>		
Charge to <b>Kerr McGee Oil &amp; Gas Onshore, LP</b>			
Address <b>1999 Broadway, Suite 3700 (XTREME 15)</b>			
City, State Zip <b>Denver, Colorado 80202</b>			
Type of Job	Depth	FL <b>952</b>	
Surface <b>8 5/8 CSG 24"</b>	Bottom of Surface	FL <b>942</b>	
Plug	Plug Landed @ <b>898</b>	FL Time On <b>0900</b>	
Production	Pipe Landed @ <b>942</b>	FL Plug Down <b>0955</b>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <b>TYPE III</b>	<b>590</b>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	<b>204</b>	Miles		
Fuel Surcharge	<b>204</b>	mes		
Additional Cement		SKS		
Mixing Rate <b>4 BPM</b>	Pre-Flush	<b>0900</b>	<b>0906</b>	
Disp. Rate <b>5 BPM</b>	Mixing	<b>0906</b>	<b>0941</b>	
Slurry Vol. <b>1.32<sup>3</sup> Cu.Ft./Sk</b>	Change Valves	<b>0941</b>	<b>0944</b>	
Slurry Wt. <b>14.8 - 15.0 PPG</b>	Displacement	<b>0944</b>	<b>0955</b>	
Water/Cement <b>6.25 Gal/SK</b>				
Water Temp. <b>51</b>				
Total Slurry Vol. <b>138.7</b>	BBLs Cement			
Landed Plug @ <b>450</b>	PSI/Final Lift @ <b>275</b>	PSI		
Pre-Flush W/ <b>30</b>	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace W/ <b>57.1</b>	BBLs H <sub>2</sub> O	State <b>CO 2.9%</b>	Tax	
Circulate <b>6</b>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<b>1201</b>		Pump Truck		<b>68</b>			
<b>1234/1235</b>		Bulk Truck		<b>68/68</b>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Jim Adam / Sason / WPU**

Received By

**Keith R. Wollen**  
Customer or His Agent

**2052918.DRI**

**80012090**