



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600312

Date	1/23/12	Well Owner	Kerr McGee	Well No	27C-25H2	Lease	Camp
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAJOR #42)						
City, State Zip	Denver, Colorado 80202						
Type of Job			Depth	Ft. 883			
Surface	9 5/8" O.D. - 36" I.D. Hole		Bottom of Surface	Ft. 882			
Plug			Plug Landed @	841	Ft.	Time On	0515
Production			Pipe Landed @	882	Ft.	Plug Down	1130

Description	Qty.	Meas.
Set Up Charge	1	
Cement Neat ✓ Type III	420	SKS
Poz. Mix		
Calcium Chloride Duaine Bell	2.5	%
Gel % Flo-Cete 1/4 # Per Sack		
User ID ZDSB4		
Mileage Charge	132	Miles
Fuel Surcharge WBS/WO/CC 2061535	132	Miles
Additional Cement G/L Acct. 30012090		SKS
Mixing Rate 4 BPM	Pre-Flush 1050-	1056
Disp. Rate 5 BPM	Mixing 1056-	1114
Slurry Vol. 1.32 ⁵ Cu.Ft./Sk	Change Valves 1114-	1117
Slurry Wt. 14.8 - 15.0 PPG	Displacement 1117-	1130
Water/Cement 6.25 Gal/SK		
Water Temp. 55° F		
Total Slurry Vol. 98.7	BBLS Cement	
Landed Plug @ 600	PSI/Final Lift @ 300	PSI
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code
Displace W/ 65	BBLS H ₂ O	State CO 2.9%
Circulate 5	BBLS Cement	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		44			
1207/1216		Bulk Truck		44/44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Steve, Chris & Evan

Received By Ramon A. Case
Customer or His Agent