

FORM
2A

Rev
04/01

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400257420

Date Received:

05/02/2012

Oil and Gas Location Assessment

☒ New Location ☐ Amend Existing Location Location#: _____

Submit original plus one copy. This form is to be submitted to the COGCC prior to any ground disturbance activity associated with oil and gas development operations. This Assessment may be approved as a standalone application or submitted as an informational report accompanying an Application for Permit-To-Drill, Form 2. Approval of this Assessment will allow for the construction of the below specified location; however, it does not supersede any land use rules applied by the local land use authority. This form may serve as notice to land owners and other interested parties, please see the COGCC web site at <http://colorado.gov/cogcc/> for all accompanying information pertinent to this Oil and Gas Location Assessment.

Location ID:

429016

Expiration Date:

05/24/2015

☒ This location assessment is included as part of a permit application.

1. CONSULTATION

- ☐ This location is included in a Comprehensive Drilling Plan. CDP # _____
- ☐ This location is in a sensitive wildlife habitat area.
- ☐ This location is in a wildlife restricted surface occupancy area.
- ☐ This location includes a Rule 306.d.(1)A.ii. variance request.

2. Operator

Operator Number: 100322

Name: NOBLE ENERGY INC

Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

3. Contact Information

Name: SUSAN MILLER

Phone: (303) 228-4246

Fax: (303) 228-4286

email: smiller@nobleenergyinc.com

4. Location Identification:

Name: WELLS RANCH Number: AA12-69-1HN

County: WELD

QuarterQuarter: NENE Section: 12 Township: 6N Range: 63W Meridian: 6 Ground Elevation: 4893

Define a single point as a location reference for the facility location. This point should be used as the point of measurement in the drawings to be submitted with this application. When the location is to be used as a well site then the point shall be a well location.

Footage at surface: 847 feet FNL, from North or South section line, and 216 feet FEL, from East or West section line.

Latitude: 40.506080 Longitude: -104.375690 PDOP Reading: 2.3 Date of Measurement: 02/16/2012

Instrument Operator's Name: Brian Brinkman

5. Facilities (Indicate the number of each type of oil and gas facility planned on location):

Special Purpose Pits: <input type="checkbox"/>	Drilling Pits: <input type="checkbox"/>	Wells: <input type="text" value="4"/>	Production Pits: <input type="checkbox"/>	Dehydrator Units: <input type="checkbox"/>
Condensate Tanks: <input type="checkbox"/>	Water Tanks: <input type="checkbox"/>	Separators: <input type="checkbox"/>	Electric Motors: <input type="checkbox"/>	Multi-Well Pits: <input type="checkbox"/>
Gas or Diesel Motors: <input type="checkbox"/>	Cavity Pumps: <input type="checkbox"/>	LACT Unit: <input type="checkbox"/>	Pump Jacks: <input type="text" value="4"/>	Pigging Station: <input type="checkbox"/>
Electric Generators: <input type="checkbox"/>	Gas Pipeline: <input type="checkbox"/>	Oil Pipeline: <input type="checkbox"/>	Water Pipeline: <input type="checkbox"/>	Flare: <input type="checkbox"/>
Gas Compressors: <input type="checkbox"/>	VOC Combustor: <input type="checkbox"/>	Oil Tanks: <input type="checkbox"/>	Fuel Tanks: <input type="checkbox"/>	

Other: One three-phase flowline will be installed at each wellhead to Econode production facility to be located 1778' south of location. See 2A doc. no. 400257385 for Wells Ranch AA12 Econode Facility.

6. Construction:

Date planned to commence construction: 09/01/2012 Size of disturbed area during construction in acres: 5.00
Estimated date that interim reclamation will begin: 12/01/2012 Size of location after interim reclamation in acres: 1.00
Estimated post-construction ground elevation: 4893 Will a closed loop system be used for drilling fluids: Yes ☒
Will salt sections be encountered during drilling: Yes ☐ No ☒ Is H2S anticipated? Yes ☐ No ☒
Will salt (>15,000 ppm TDS Cl) or oil based muds be used: Yes ☐ No ☒
Mud disposal: Offsite ☒ Onsite ☐ Method: Land Farming ☒ Land Spreading ☐ Disposal Facility ☐
Other: _____

7. Surface Owner:

Name: _____ Phone: _____
Address: _____ Fax: _____
Address: _____ Email: _____
City: _____ State: _____ Zip: _____ Date of Rule 306 surface owner consultation: 02/16/2012
Surface Owner: ☒ Fee ☐ State ☐ Federal ☐ Indian
Mineral Owner: ☒ Fee ☐ State ☐ Federal ☐ Indian
The surface owner is: ☐ the mineral owner ☐ committed to an oil and gas lease
☐ is the executer of the oil and gas lease ☐ the applicant
The right to construct the location is granted by: ☐ oil and gas lease ☒ Surface Use Agreement ☐ Right of Way
☐ applicant is owner
Surface damage assurance if no agreement is in place: ☐ \$2000 ☐ \$5000 ☐ Blanket Surety ID _____

8. Reclamation Financial Assurance:

☒ Well Surety ID: 20030009 ☐ Gas Facility Surety ID: _____ ☐ Waste Mgmt. Surety ID: _____

9. Cultural:

Is the location in a high density area (Rule 603.b.): Yes ☐ No ☒
Distance, in feet, to nearest building: 5280, public road: 5280, above ground utilit: 5280
, railroad: 5280, property line: 216

10. Current Land Use (Check all that apply):

Crop Land: ☐ Irrigated ☐ Dry land ☐ Improved Pasture ☐ Hay Meadow ☐ CRP
Non-Crop Land: ☒ Rangeland ☐ Timber ☐ Recreational ☐ Other (describe): _____
Subdivided: ☐ Industrial ☐ Commercial ☐ Residential

11. Future Land Use (Check all that apply):

Crop Land: ☐ Irrigated ☐ Dry land ☐ Improved Pasture ☐ Hay Meadow ☐ CRP
Non-Crop Land: ☒ Rangeland ☐ Timber ☐ Recreational ☐ Other (describe): _____
Subdivided: ☐ Industrial ☐ Commercial ☐ Residential

12. Soils:

List all soil map units that occur within the proposed location. Attach the National Resource Conservation Service (NRCS) report showing the "Map Unit Description" report listing the soil typical vertical profile. This data is to used when segregating topsoil.

The required information can be obtained from the NRCS web site at <http://soildatamart.nrcs.usda.gov/> or from the COGCC web site GIS Online map page found at <http://colorado.gov/cogcc>. Instructions are provided within the COGCC web site help section.

NRCS Map Unit Name: 72: Vona loamy sand, 0-3% slopes

NRCS Map Unit Name: _____
NRCS Map Unit Name: _____

13. Plant Community:

Complete this section only if any portion of the disturbed area of the location's current land use is on non-crop land.

Are noxious weeds present: Yes ☐ No ☒
Plant species from: ☐ NRCS or, ☒ field observation Date of observation: 02/16/2012
List individual species: _____

Check all plant communities that exist in the disturbed area.

- ☐ Disturbed Grassland (Cactus, Yucca, Cheatgrass, Rye)
☒ Native Grassland (Bluestem, Grama, Wheatgrass, Buffalograss, Fescue, Oatgrass, Brome)
☐ Shrub Land (Mahogany, Oak, Sage, Serviceberry, Chokecherry)
☐ Plains Riparian (Cottonwood, Willow, Aspen, Maple, Poplar, Russian Olive, Tamarisk)
☐ Mountain Riparian (Cottonwood, Willow, Blue Spruce)
☐ Forest Land (Spruce, Fir, Ponderosa Pine, Lodgepole Pine, Juniper, Pinyon, Aspen)
☐ Wetlands Aquatic (Bullrush, Sedge, Cattail, Arrowhead)
☐ Alpine (above timberline)
☐ Other (describe): _____

14. Water Resources:

Rule 901.e. may require a sensitive area determination be performed. If this determination is performed the data is to be submitted with the Form 2A.

Is this a sensitive area: ☒ No ☐ Yes Was a Rule 901.e. Sensitive Areas Determination performed: ☒ No ☐ Yes
Distance (in feet) to nearest surface water: 493, water well: 4112, depth to ground water: 120
Is the location in a riparian area: ☒ No ☐ Yes Was an Army Corps of Engineers Section 404 permit filed ☒ No ☐ Yes
Is the location within a Rule 317B Surface Water Supply Area buffer zone:
☒ No ☐ 0-300 ft. zone ☐ 301-500 ft. zone ☐ 501-2640 ft. zone

If the location is within a Rule 317B Surface Water Supply Area buffer have all public water supply systems within 15 miles been notified: ☐ No ☐ Yes

15. Comments:

Nearest building, public road, above ground utility, railroad. Nearest water well permit no. 10790 (stock). Reference area located immediately adjacent to and north of location on undisturbed land as shown on attached photo.

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct and complete.

Signed: _____ Date: 05/02/2012 Email: smiller@nobleenergyinc.com
Print Name: SUSAN MILLER Title: Regulatory Analyst III

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 5/25/2012

**CONDITIONS OF
APPROVAL, IF ANY:** _____

All representations, stipulations and conditions of approval stated in this Form 2A for this location shall constitute representations, stipulations and conditions of approval for any and all subsequent operations on the location unless this Form 2A is modified by Sundry Notice, Form 4 or an Amended Form 2A.

Attachment Check List

Att Doc Num	Name
2613978	REFERENCE AREA PICTURES
400257420	FORM 2A SUBMITTED
400257422	ACCESS ROAD MAP
400257423	HYDROLOGY MAP
400257424	LOCATION DRAWING
400257425	LOCATION PICTURES
400257426	MULTI-WELL PLAN
400257427	WASTE MANAGEMENT PLAN
400257429	NRCS MAP UNIT DESC
400280025	SURFACE AGRMT/SURETY

Total Attach: 10 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	No LGD or public comment received; final review completed.	5/24/2012 1:33:56 PM
OGLA	Attached revised Reference Area Picture from operator - the Reference Area is west of the location; initial review complete, comment period expires 5/23	5/16/2012 8:11:57 AM
OGLA	waiting on revised Reference Area information from operator	5/8/2012 1:15:17 PM

Total: 3 comment(s)

BMP

Type	Comment
Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
Drilling/Completion Operations	<p>Anti-collision: Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.</p> <p>During and Post stimulation: 1. At least seven (7) days prior to fracture stimulation, the Operator is to notify all operators of non-operated wells within 300 feet of the wellbore to be fracture stimulated of the anticipated date stimulation date and the recommended best management practice to shut-in all wells within 300' of the stimulated wellbore completed in the same formation.</p> <p>2. The Operator will monitor the bradenhead pressure of all wells operated by the Operator within 300 feet of the well to be fracture stimulated.</p> <p>3. Bradenhead pressure gauges are to be installed 24 hours prior to stimulation. The gauges are to read at least once during every 24-hour period until 24-hours after stimulation is completed (post flowback). The gauges are to be of the type able to read current pressure and record the maximum encountered pressure in a 24-hour period. The gauge is to be reset between each 24-hour period. The pressures are to be recorded and saved. Alternate electronic measurement may be used to record the prescribed pressures. Data shall be kept for a period of one year.</p> <p>4. If at any time during stimulation or the 24-hour post-stimulation period, the bradenhead annulus pressure of the treatment well or offset wells increases more than 200 psig, as per Rule 341, the Operator of the well being stimulated shall verbally notify the Director as soon as practicable, but no later than twenty-four (24) hours following the incident. Within fifteen (15) days after the occurrence, the Operator shall submit a Sundry Notice, Form 4, giving all details, including corrective actions taken.</p>
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) and General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location and will remain in place until the pad reaches final reclamation.
General Housekeeping	General housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur, prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
Total: 4 comment(s)	