

FORM
17Rev
6/99

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400288963			

BRADENHEAD TEST REPORT

Step 1. Record all tubing and casing pressures as found. Step 2. Sample now. If intermediate or surface casing pressure > 25 psi. In sensitive areas, 1 psi.
 Step 3. Conduct Bradenhead test. Step 4. Conduct intermediate casing test. Step 5. Send report to BLM within 3 days and to OGCC within 10 days. Include wellbore diagram if not previously submitted or if wellbore configuration has changed since prior program. Attach gas and liquid analyses if sampled.

1. OGCC Operator Number: 47120 3. BLM Lease No: _____
 2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP
 4. API Number: 05-123-28043-00 5. Multiple completion? ☐ Yes ☐ No
 6. Well Name: WILLIAMS Number: 11-20
 7. Location (QtrQtr, Sec, Twp, Rng, Meridian): NWSE,20,2N,68W,6
 8. County WELD 9. Field Name: SPINDLE
 10. Minerals: ☐ Fee ☐ State ☐ Federal ☐ Indian

11. Date of Test: 05/01/2012

12. Well Status: ☐ Flowing
☐ Shut In ☐ Gas Lift
☐ Pumping ☐ Injection
☐ Clock/Intermitter
☒ Plunger Lift

13. Number of Casing Strings:
☐ Two ☐ Three ☐ Liner?

14. EXISTING PRESSURES

Record all pressures as found	Tubing: 480	Tubing: _____	Prod Csg 527	Intermediate	Surf. Csg
	Fm: _____	Fm: _____	Fm: _____	Csg: _____	309

BRADENHEAD TEST

Buried valve? ☐ Yes ☒ No
 Confirmed open? ☒ Yes ☐ No
 With gauges monitoring production, intermediate casing and tubing pressures, open surface casing (bradenhead) valve (if no intermediate casing, monitor only the production casing and tubing pressures.) Record pressures at five minute intervals Define characteristics of flow in "Bradenhead Flow" column using letter designations below:
 O = No Flow; C = Continuous; D = Down to 0; V = Vapor
 H = Water H2O; M = Mud; W = Whisper; S = Surge; G = Gas

BRADENHEAD SAMPLE TAKEN?
☐ Yes ☒ No ☐ Gas ☐ Liquid

Character of Bradenhead fluid: ☐ Clear ☐ Fresh
☐ Sulfur ☐ Salty ☐ Black

Other:(describe)

Sample cylinder number:

Elapsed Time (Min:Sec)	Fm: Tubing	Fm: Tubing:	Prod Csg PSIG	Intermedia Csg PSIG	Bradenhead Flow:
00:00	<input type="checkbox"/> 480	<input type="checkbox"/>	<input type="checkbox"/> 527		G
05:00	<input type="checkbox"/> 483	<input type="checkbox"/>	<input type="checkbox"/> 530		G
10:00	<input type="checkbox"/> 485	<input type="checkbox"/>	<input type="checkbox"/> 532		G
15:00	<input type="checkbox"/> 487	<input type="checkbox"/>	<input type="checkbox"/> 534		G
20:00	<input type="checkbox"/> 491	<input type="checkbox"/>	<input type="checkbox"/> 538		G
25:00	<input type="checkbox"/> 494	<input type="checkbox"/>	<input type="checkbox"/> 541		G
30:00	<input type="checkbox"/> 496	<input type="checkbox"/>	<input type="checkbox"/> 542		G

Instantaneous Bradenhead PSIG at end of test: > 96

INTERMEDIATE CASING TEST

Buried valve? ☐ Yes ☐ No
 Confirmed open? ☐ Yes ☐ No
 With gauges monitoring production, intermediate casing and tubing pressures, open the intermediate casing valve. Record pressures at five minute intervals Characterize flow in "Intermediate Flow" column using letter designations below:
 O = No Flow; C = Continuous; D = Down to 0; V = Vapor
 H = Water H2O; M = Mud; W = Whisper; S = Surge; G = Gas

INTERMEDIATE SAMPLE TAKEN?
☐ Yes ☐ No ☐ Gas ☐ Liquid

Character of Intermediate fluid: ☐ Clear ☐ Fresh
☐ Sulfur ☐ Salty ☐ Black

Other:(describe)

Sample cylinder number:

Elapsed Time (Min:Sec)	Fm: Tubing	Fm: Tubing:	Prod Csg PSIG	Intermedia Csg PSIG	Bradenhead Flow:
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		

Instantaneous Intermediate Casing PSIG at end of test: >

Comments:

No fluid was produced during 30 minute blow down

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Test Performed By: Jessica Coakley Title: Non-Employee Job Phone: (970) 580-8946

Signed: Rebecca Murphy Title: Non-Employee Job Date: 5/25/2012

Witnessed By: _____ Title: _____ Agency: _____