

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400275556

Date Received:

05/02/2012

PluggingBond SuretyID

20030009

APPLICATION FOR PERMIT TO:

1. ☐ Drill, ☐ Deepen, ☐ Re-enter, ☒ **Recomplete and Operate**

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☐

Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: Andrea Rawson Phone: (303)228-4253 Fax: (303)228-4286

Email: arawson@nobleenergyinc.com

7. Well Name: Miller P Well Number: 27-04Ji

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7762

WELL LOCATION INFORMATION

10. QtrQtr: NWNw Sec: 27 Twp: 3N Rng: 67W Meridian: 6

Latitude: 40.201850 Longitude: -104.884310

Footage at Surface: 469 feet FNL 457 feet FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4810 13. County: WELD

14. GPS Data:

Date of Measurement: 11/05/2006 PDOP Reading: 2.1 Instrument Operator's Name: Paul Tappy

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 200 ft

18. Distance to nearest property line: 195 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1150 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL	407-87	80	W/2NW/4
Niobrara	NBRR	407-87	80	W/2NW/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T3N, R67W, Sec 27: W/2W/2

25. Distance to Nearest Mineral Lease Line: 195 ft

26. Total Acres in Lease: 138

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	406	285	626	0
1ST	7+7/8	4+1/2	11.6	0	7,756	150	7,756	6,800

32. BOP Equipment Type: ☐ Annular Preventer ☐ Double Ram ☐ Rotating Head ☒ None

33. Comments A Form 2A is not required for this recompletion because no pit will be constructed and there will be no additional surface disturbance beyond the originally disturbed area. No conductor casing will be set. A form 4 has already been sent in.

34. Location ID: 331105

35. Is this application in a Comprehensive Drilling Plan? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Andrea Rawson

Title: Regulatory Specialist Date: 5/2/2012 Email: arawson@nobleenergyinc.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 5/25/2012

API NUMBER

05 123 20159 00

Permit Number: _____ Expiration Date: 5/24/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Provide cement bond log to verify isolation of Shannon. 2) If this work has not been performed, then provide remedial cement coverage from 200' below Shannon to 200' above Shannon (minimum coverage 4840' to 4440'). Verify remedial coverage with cement bond log.

Attachment Check List

Att Doc Num	Name
400275556	FORM 2 SUBMITTED
400280145	SURFACE AGRMT/SURETY

Total Attach: 2 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed. No LGD or public comment received.	5/24/2012 2:08:59 PM
Permit	Operator confirmed 40.20185 and 104.88431 for actual lat/longs. ok to pass.	5/23/2012 9:32:13 AM
Permit	ON HOLD: w/o confirmation of lat/longs.	5/23/2012 9:03:34 AM
Permit	Form 4 document # 2288477.	5/8/2012 10:19:15 AM

Total: 4 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)