

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400280215

Date Received:

05/02/2012

PluggingBond SuretyID

20040105

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER ☐
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: BERRY PETROLEUM COMPANY

4. COGCC Operator Number: 10091

5. Address: 1999 BROADWAY STE 3700

City: DENVER State: CO Zip: 80202

6. Contact Name: HEIDI BANG Phone: (303)999-4262 Fax: (303)999-4362

Email: HSB@BRY.COM

7. Well Name: BERRY Well Number: 1-33D

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 10200

WELL LOCATION INFORMATION

10. QtrQtr: Lot 10 Sec: 1 Twp: 6S Rng: 97W Meridian: 6

Latitude: 39.555987 Longitude: -108.171253

Footage at Surface: 3064 feet FNL/FSL 1924 feet FEL/FWL
FNL FWL

11. Field Name: GRAND VALLEY Field Number: 31290

12. Ground Elevation: 8320 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 04/09/2007 PDOP Reading: 2.5 Instrument Operator's Name: ROBERT WOOD

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
3420 FNL 660 FWL 3420 FNL 660 FWL
Sec: 1 Twp: 6S Rng: 97W Sec: 1 Twp: 6S Rng: 97W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 15387 ft

18. Distance to nearest property line: 586 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 318 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	510-25	553	N/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #:

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

PLEASE SEE MINERAL LEASE ATTACHED TO ORIGINAL APD ON FILE.

25. Distance to Nearest Mineral Lease Line: 2829 ft

26. Total Acres in Lease: 5165

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	30	20	55	0	90	100	90	0
SURF	16	9+5/8	36	90	2,000	1,000	2,000	0
1ST	8+3/4	4+1/2	11.6	2000	10,200	600	10,200	200

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Berry Petroleum owns surface. COGCC Facility ID # 335716I certify that there have been no changes on land use, lease description. The pad has been built. The pits have been constructed. Wells have been drilled. No rig on site. The refile will not require any expansion / additional surface disturbance of the pad. The location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii). The location is not in a wildlife restricted surface occupancy area.

34. Location ID: 335716

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: HEIDI BANG

Title: REG COMPLIANCE ASST

Date: 5/2/2012

Email: HSB@BRY.COM

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____

Director of COGCC

Date: 5/25/2012

API NUMBER

05 045 14622 00

Permit Number: _____ Expiration Date: 5/24/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(3) OPERATOR MUST ENSURE 110 PERCENT SECONDARY CONTAINMENT FOR ANY VOLUME OF FLUIDS CONTAINED AT WELL-SITE DURING DRILLING AND COMPLETION OPERATIONS. IF FLUIDS ARE CONVEYED VIA PIPELINE, OPERATOR MUST IMPLEMENT BEST-MANAGEMENT-PRACTICES TO CONTAIN ANY UNINTENTIONAL RELEASE OF FLUIDS.

(4) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

(5) NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT. THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT.

(6) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST CURRENTLY-PERMITTED WATER WELL WITHIN 1-MILE IS 00 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400280215	FORM 2 SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	LGD waived;public comments waived. Final Review--passed.	5/24/2012 8:40:27 AM
Permit	Changed qtr/qtr to Lot 10, checked "NO" for #36. Confirmed pad is built, No 2A required.	5/18/2012 7:56:54 AM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)