

FORM
5Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400262213

Date Received:

03/29/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100322

4. Contact Name: Liz Lindow

2. Name of Operator: NOBLE ENERGY INC

Phone: (303) 228-4342

3. Address: 1625 BROADWAY STE 2200

Fax:

City: DENVER State: CO Zip: 80202

5. API Number 05-123-34352-00

6. County: WELD

7. Well Name: BUROUGH C

Well Number: 23-30D

8. Location: QtrQtr: NESW Section: 14 Township: 4N Range: 64W Meridian: 6

Footage at surface: Distance: 1476 feet Direction: FSL Distance: 1445 feet Direction: FWL

As Drilled Latitude: 40.309280 As Drilled Longitude: -104.522148

GPS Data:

Date of Measurement: 12/28/2011 PDOP Reading: 4.5 GPS Instrument Operator's Name: Paul Tappy

** If directional footage at Top of Prod. Zone Dist.: 71 feet. Direction: FSL Dist.: 497 feet. Direction: FWL

Sec: 14 Twp: 4N Rng: 64W

** If directional footage at Bottom Hole Dist.: 70 feet. Direction: FSL Dist.: 499 feet. Direction: FWL

Sec: 14 Twp: 4N Rng: 64W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 11/26/2011 13. Date TD: 11/29/2011 14. Date Casing Set or D&A: 11/30/2011

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7240 TVD** 6928 17 Plug Back Total Depth MD 7187 TVD** 6875

18. Elevations GR 4648 KB 4662

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL/CCL/GR; Caliper/Comp. Density/Neutron/GR/SP/ML; DIL/FR/SP/Caliper

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	686	305	0	686	VISU
1ST	7+7/8	4+1/2	11.6	0	7,232	580	1,877	7,232	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____					
Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
Details of work:					

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
NIOBRARA	6,797		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,054		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,077		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Hard copies of logs sent to COGCC 3/21/2012.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Liz Lindow

Title: Regulatory Analyst Date: 3/29/2012 Email: llindow@noblenergyinc.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400263375	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400262228	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400262213	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400262716	LAS-TRIPLE COMBINATION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400262718	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400266291	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	Logs received 4/20/2012	5/14/2012 10:48:48 AM
Permit	No hard copy logs have been sent. Requested from operator	4/19/2012 8:01:58 AM

Total: 2 comment(s)