

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400274362

Date Received:

04/25/2012

PluggingBond SuretyID

20100083

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER ☐ Pilot Hole ☐
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐3. Name of Operator: AXIA ENERGY LLC4. COGCC Operator Number: 103355. Address: 1430 LARIMER STREET #400City: DENVER State: CO Zip: 802026. Contact Name: Lisa Smith Phone: (303)857-9999 Fax: (303)450-9200Email: Ispermitco@aol.com7. Well Name: Bulldog Well Number: 20-12H-892

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 12000

WELL LOCATION INFORMATION

10. QtrQtr: SWNW Sec: 20 Twp: 8N Rng: 92W Meridian: 6Latitude: 40.632925 Longitude: -107.750883

Footage at Surface: 1641 feet FNL/FSL 712 feet FEL/FWL
 FNL FWL

11. Field Name: Lay Creek Field Number: 4855012. Ground Elevation: 6845 13. County: MOFFAT

14. GPS Data:

Date of Measurement: 03/15/2012 PDOP Reading: 1.3 Instrument Operator's Name: Glenn McElroy15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 5280 ft18. Distance to nearest property line: 321 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 5280 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T8N - R92W: Section 19: E2SE, SENE Section 20: SWSW, S2NW, N2SW

25. Distance to Nearest Mineral Lease Line: 321 ft

26. Total Acres in Lease: 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☒ Yes ☐ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	55	0	60	60	60	0
SURF	13+1/2	10+3/4	40.5	0	1,500	545	1,500	0
1ST	9+7/8	7+5/8	29.7	0	8,500	850	8,500	3,000
OPEN HOLE	6+3/4			0	12,000	470	12,000	10,220

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments This is a Pilot Hole for informational purposes only.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Lisa Smith

Title: Authorized Agent Date: 4/25/2012 Email: lspermitco@aol.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 5/31/2012

API NUMBER

05 081 07729 00

Permit Number: _____ Expiration Date: 5/30/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Before placing oil/salt based muds in a pit, operator must file and receive prior approval of a Pit Permit, Form 15. COGCC regulations regarding pit permits can be found in Rule 903.a.(3). PIT PERMITTING/REPORTING REQUIREMENTS.

1)COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2)PROVIDE CEMENT COVERAGE FROM THE 7-5/8" CASING SHOE TO A MINIMUM OF 200' ABOVE TOP OF GAS [OR OTHER SHALLOWEST-KNOWN PRODUCING HORIZON]. VERIFY CEMENT WITH A CEMENT BOND LOG.

3)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 690 FEET DEEP.

Attachment Check List

Att Doc Num	Name
1533105	SURFACE AGRMT/SURETY
1533118	SURFACE AGRMT/SURETY
400274362	FORM 2 SUBMITTED
400276752	WELL LOCATION PLAT

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Off Hold--attached vol. pooling declaration map to horizontal permit. Changed dist. to nearest min. lease to 321'. LGD/pub. comments waived. Final Review--passed.	5/29/2012 10:46:59 AM
Permit	Attached SUA Memo emailed by oper. Confirmed that spacing & hearing application for 5/29/20125 hearing has been withdrawn. Now a voluntary pooling drilling unit. Removed surface bond. This well will not be completed.	5/18/2012 10:33:30 AM
Permit	Rec'd. confirmation that spacing and pooling applications have been withdrawn.	5/17/2012 8:58:52 AM
Permit	May Docket application: UP 142 & SP 53.	5/1/2012 9:50:35 AM

Total: 4 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)