

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400284202

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☒

Sidetrack ☐

PluggingBond SuretyID

20040071

3. Name of Operator: ANTERO RESOURCES PICEANCE CORPORATION

4. COGCC Operator Number: 10079

5. Address: 1625 17TH ST STE 300

City: DENVER State: CO Zip: 80202

6. Contact Name: Shauna Redican Phone: (303)357-6820 Fax: (303)357-7315

Email: sredican@anteroresources.com

7. Well Name: North Bank Well Number: C9

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 14359

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 12 Twp: 6S Rng: 93W Meridian: 6

Latitude: 39.539539 Longitude: -107.727142

Footage at Surface: 2148 feet FNL/FSL 1905 feet FEL/FWL FSL FWL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 5352 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 10/13/2006 PDOP Reading: 1.3 Instrument Operator's Name: Samuel D. Phelps

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2267 FSL 1820 FWL 2267 FSL 1820 FWL
Bottom Hole: FNL/FSL 2267 FSL 1820 FWL
Sec: 12 Twp: 6S Rng: 93W Sec: 12 Twp: 6S Rng: 93W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1326 ft

18. Distance to nearest property line: 965 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 479 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	191-25		
Mancos	MNCS	191-60		
Williams Fork	WMFK	510-16		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T6S-R93W: Section 12 (part of section)- Please see previously submitted Plat #6

25. Distance to Nearest Mineral Lease Line: 1000 ft 26. Total Acres in Lease: 241

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Bury onsite if meets Table

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	55#	0	60	177	60	0
SURF	12+1/4	8+5/8	24/32#	0	1,000	416	1,000	0
1ST	7+7/8	4+1/2	11.6#	0	14,359	763	14,359	

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments I certify that all conditions in the original permit are the same except the updated casing and cement program. There have been no other changes to land use, well construction or the lease. This Refile Form 2 does not require a Form 2A because the pad has been constructed, a closed loop system is being used so no pits need to be constructed, the refiled well will not require any expansion / additional surface disturbance of the pad. The location is not in a wildlife restricted surface occupancy area (RSO); consultation with CDOW is not required and the location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii).; consultation with CDPHE is not required.#31 Mud Disposal: Antero will bury onsite if disposal meets Table 910 and if there is a provision in SUA which allows for such operation. TOP OF CEMENT OF 1ST STRING/PRODUCTION CASING WILL BE >500 FEET ABOVE TOP OF GAS.

34. Location ID: 336013

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Shauna Redican

Title: Permit Representative Date: _____ Email: sredican@anteroresources.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05 045 13617 00

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400287134	30 DAY NOTICE LETTER

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)