



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600384

Date <u>2-24-12</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>16N-27HZ</u>	Lease <u>GOBBLER</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (MAJOR #44)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl. <u>1022</u>	
<u>Surface</u>	<u>9 5/8" CSG 36# 13 1/2 H2O</u>	Bottom of Surface	Fl. <u>1011</u>
Plug	Plug Landed @ <u>969</u>	Fl.	Time On <u>1630</u>
Production	Pipe Landed @ <u>7011</u>	Fl.	Plug-Down <u>1900</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>TYPE III 100% EXCESS</u>	<u>750</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel. % Flo-Cete 1/4 # Per Sack				
Mileage Charge <u>2056939</u>	<u>159</u>	Miles		
Fuel Surcharge <u>80012090</u>	<u>159</u>	MILES		
Additional Cement	<u>60</u>	SKS		
Mixing Rate 4 BPM	Pre-Flush	<u>1746</u>	<u>1754</u>	
Disp. Rate 5 BPM	Mixing	<u>1754</u>	<u>1842</u>	
Slurry Vol. 1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	<u>1842</u>	<u>1845</u>	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	<u>1845</u>	<u>1900</u>	
Water/Cement 6.25 Gal/SK				
Water Temp. <u>-38°F</u>				
Total Slurry Vol. <u>190.4</u>	BBLS Cement			
Landed Plug @ <u>1000</u>	PSI/Final Lift @ <u>350</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace W/ <u>74.9</u>	BBLS H <sub>2</sub> O	State <u>CO 2.9%</u>	Tax	
Circulate <u>4</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>		Pump Truck		<u>53</u>			
<u>1234/1218</u>		Bulk Truck		<u>53/53</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM, ADAM, JASON, JOSH

Received By J E Rose  
Customer or His Agent