



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600387

Date	2/24/12	Well Owner	Kerr McGee	Well No.	9c-29HZ	Lease	Howard
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Xtreme 20)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	1175		
Surface	9 5/8 CSG 36" 13 1/2" Hole	Bottom of Surface		Fl.	1153		
Plug		Plug Landed @	1110	Ft.	Time On	2000	
Production		Pipe Landed @	1153	Ft.	Plug Down	0000	

Description	Qty.	Meas.
Set Up Charge	1	
Cement Neat TYPE III	860	SKS
Poz. Mix		
Calcium Chloride	2.5	%
Gel. % Flo-Cete 1/4 # Per Sack		
Mileage Charge	210	Miles
Fuel Surcharge	210	Miles
Additional Cement	800/2090	SKS
Mixing Rate	4 BPM	Pre-Flush
Disp. Rate	5 BPM	Mixing
Slurry Vol.	1.32 ³ Cu. Ft./Sk	Change Valves
Slurry Wt.	14.8 - 15.0 PPG	Displacement
Water/Cement	6.25 Gal/SK	
Water Temp.	62°F	
Total Slurry Vol.	202.1	BBLs Cement
Landed Plug @	1000	PSI/Final Lift @ 425 PSI
Pre-Flush W/	30	BBLs H ₂ O
Displace W/	85.8	BBLs H ₂ O
Circulate	4	BBLs Cement
		Tax Reference Code
		Sub Total
		Tax
		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		70			
1218/1234		Bulk Truck		70/70			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim, Adam, Jason, Josh

Received By

Charles L. Dwyer
Customer or His Agent