



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600389

Date	2/29/12	Well Owner	Kerr McGee	Well No.	17-10	Lease	Stear
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Xtreme 14)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	742		
Surface	8 5/8 CSG 24"	Bottom of Surface		Fl.	732		
Plug		Plug Landed @	688	Fl.	Time On	0515	
Production		Pipe Landed @	732	Fl.	Plug Down	0915	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	460	SKS		
Poz. Mix	2149897 lbs			
Calcium Chloride	2.5	%		
Gal % Flo-Cote 1/4 # Per Sack	8002090			
Mileage Charge	150	Miles		
Fuel Surcharge	150	mils		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	0933	0937
Disp. Rate	5 BPM	Mixing	0937	0904
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	0904	0907
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0907	0915
Water/Cement	6.25 Gal/SK			
Water Temp.	60°F			
Total Slurry Vol.	109.4	BBLs Cement		
Landed Plug @	350	PSI/Final Lift @	125	PSI
Pre-Flush Wt	20	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace Wt	43.7	BBLs H ₂ O	State CO 2.9%	Tax
Circulate	5	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		50			
1214/1216		Bulk Truck		50/50			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim, Adam, Jason, Will, Eric

Received By Customer or His Agent