



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600176

Date	10-29-11	Well Owner	Kerr McGee	Well No.	28-32	Lease	HOWARD
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME-15)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	Ft. 1220				
Surface	8 5/8" CSG-24#	Bottom of Surface	Ft. 1213				
Plug		Plug Landed @	1171	Ft.	Time On	1315	
Production		Pipe Landed @	1213	Ft.	Plug Down	1700	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat	760	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel. % Flo-Cete 1/4 # Per Sack	9057897			
Mileage Charge	144	Miles		
Fuel Surcharge	144	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1549	-1557
Disp. Rate	5 BPM	Mixing	1557	-1642
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	1642	-1645
Slurry WL	14.8 - 15.0 PPG	Displacement	1645	-1700
Water/Cement	6.25 Gal/SK			
Water Temp.	42° F			
Total Slurry Vol.	178.6	BBLs Cement		
Landed Plug @	1000	PSI/Final Lift @	400	PSI
Pre-Flush W/	30	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace W/	74.4	BBLs H ₂ O	State CO 2.9%	Tax
Circulate	4	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1209		Pump Truck		72			
1234/1007		Bulk Truck		72			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Joe JOSH, EVAN, ERNIE

Received By *Mr. Z. Kelly*
Customer or His Agent