



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 338220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600030

Date <u>9-13-11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>37-29</u>	Lease <u>HOWARD</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (X-TRAIL #15)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl.	
<u>Surface</u>	<u>8 5/8" CSG - 2' 11"</u>	<u>1174</u>	
Plug	Bottom of Surface	Fl.	
		<u>1184</u>	
Production	Plug Landed @ <u>1138</u>	Fl.	Time On <u>1315</u>
	Pipe Landed @ <u>1184</u>	Fl.	Plug Down <u>1700</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>TYPE III</u>	750	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack <u>20547745 DRK</u>				
Mileage Charge <u>80012090</u>	204	Miles		
Fuel Surcharge	204	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	1550	1558	
Disp. Rate 5 BPM	Mixing	1558	1642	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	1642	1645	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1645	1700	
Water/Cement 6.25 Gal/SK				
Water Temp. <u>68°F</u>				
Total Slurry Vol. <u>176.3</u>	BBLS Cement			
Landed Plug @ <u>1000</u>	PSI/Final Lift @ <u>500</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>72.3</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>5</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1202</u>		Pump Truck		<u>68</u>			
<u>1211/1216</u>		Bulk Truck		<u>68/68</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, EVAN, ERNIE

Received By [Signature]
Customer or His Agent