



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600395

Date	3/17/2012	Well Owner	Kerr McGee	Well No.	24N-25H2	Lease	Howard
County		State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #20)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	1185		
Surface	9 5/8 CSG 3/4" 13 1/2 HOLE	Bottom of Surface		Ft.	1176		
Plug		Plug Landed @	1138	Ft.	Time On	0400	
Production		Plug Landed @	1176	Ft.	Plug Down	1030	
Description				Qty.	Meas.		
Set Up Charge				1			
Cement Neat	TYPE III			870	SKS		
Poz. Mix							
Calcium Chloride				2.5	%		
Gel %	Fio-Cete 1/4 # Per Sack						
Mileage Charge				270	Miles		
Fuel Surcharge				270	MILES		
Additional Cement					SKS		
Mixing Rate	4 BPM	Pre-Flush		0913	0919		
Disp. Rate	5 BPM	Mixing		0919	1010		
Slurry Vol.	1.32 ³ Cu. Ft./Sk	Change Valves		1010	1013		
Slurry Wt.	14.8 - 15.0 PPG	Displacement		1013	1030		
Water/Cement	6.25 Gal/SK						
Water Temp.	56						
Total Slurry Vol.	204.5	BBLs Cement					
Landed Plug @	980	PSI/Final Lift @	270	PSI			
Pre-Flush W/	30	DDL3 H ₂ O	Tax Reference Code	Sub Total			
Displace W/	87.5	BBLs H ₂ O	State	CO 2.9%	Tax		
Circulate	3	BBLs Cement		Total			
Great Job & very professional J.E.							
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		90			
1234/1216		Bulk Truck		90/90			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM/ADAM/JASON

Received By J.E. Mugg 17-Mar-12
Customer or His Agent