

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400289146

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Erin Hochstetler Phone: (720)876-5827 Fax: ()

Email: erin.hochstetler@encana.com

7. Well Name: WhF Well Number: DHS3C-20 D17998

8. Unit Name (if appl): Jackson Canyon Unit Number: 047641X

9. Proposed Total Measured Depth: 16951

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 17 Twp: 9S Rng: 98W Meridian: 6

Latitude: 39.277539 Longitude: -108.358839

Footage at Surface: 958 feet FNL/FSL 827 feet FEL/FWL
FNL FWL

11. Field Name: Bronco Flats Field Number: 7563

12. Ground Elevation: 5771 13. County: MESA

14. GPS Data:

Date of Measurement: 03/22/2012 PDOP Reading: 1.9 Instrument Operator's Name: Ted Taggart

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 686 FNL 1918 FEL 28 FSL 1950 FEL
Sec: 17 Twp: 9S Rng: 98W Sec: 20 Twp: 9S Rng: 98W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 515 ft

18. Distance to nearest property line: 7709 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1285 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Mancos	MNCS			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

COC 12645 (SHL) T9S-98W-Sec. 17: All - COC 12645A (BHL) T9S-R98W-Sec. 18: Lots 1-4, E/2W/2, E/2 Sec. 19: Lots 1-4, NENW, NE, SENW, SE, Sec. 20: W/2SW

25. Distance to Nearest Mineral Lease Line: 28 ft

26. Total Acres in Lease: 1827

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Recycle & Bury

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	30	20	line pipe	0	120	319	120	0
SURF	14+3/4	10+3/4	41	0	1,000	469	1,000	0
2ND	9+7/8	7+5/8	26	0	5,500	746	5,500	0
3RD	6+3/4	4+1/2	12	0	16,951	1,015	16,951	200

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Encana is proposing a new unit in this area. Third string casing will be either 4 1/2 or 5 1/2 with weight as 12# and 17# respectively. The top of cement will be 200' above Mancos.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Erin Hochstetler

Title: Permitting Technician Date: _____ Email: erin.hochstetler@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400294535	WELL LOCATION PLAT
400294538	DEVIATED DRILLING PLAN
400294677	DIRECTIONAL DATA

Total Attach: 3 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)

BMP

Type	Comment
Wildlife	<ul style="list-style-type: none">• Prohibit Encana employees and contractors from carrying projectile weapons on Encana leases.• Prohibit pets on Encana leases.• Strategically apply fugitive dust control measures, including enforcing established speed limits on Encana private roads, to reduce fugitive dust and coating of vegetation and deposition in water sources.
Construction	<ul style="list-style-type: none">• Use solar panels as an alternative energy source for on-location production equipment, where appropriate, economically and technically feasible.• Use multiple gathering lines placed in a single trench to minimize disturbance and construction, where appropriate, economically and technically feasible.• Install pipeline crossings at right angles to the drainages, wetlands, and perennial water bodies, where appropriate, economically and technically feasible.

Total: 2 comment(s)