

FORM
5

Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400268618

Date Received:

04/05/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: Julie Lawson

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 260-4533

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-045-20509-00

6. County: GARFIELD

7. Well Name: Bosely

Well Number: SG 413-23

8. Location: QtrQtr: NWSW Section: 23 Township: 7S Range: 96W Meridian: 6

Footage at surface: Distance: 2136 feet Direction: FSL Distance: 1395 feet Direction: FWL

As Drilled Latitude: 39.421734 As Drilled Longitude: -108.082071

GPS Data:

Data of Measurement: 08/30/2011 PDOP Reading: 2.2 GPS Instrument Operator's Name: J. Kirkpatrick

** If directional footage at Top of Prod. Zone Dist.: 2119 feet. Direction: FSL Dist.: 1026 feet. Direction: FWL

Sec: 23 Twp: 7S Rng: 96W

** If directional footage at Bottom Hole Dist.: 2112 feet. Direction: FSL Dist.: 1000 feet. Direction: FWL

Sec: 23 Twp: 7S Rng: 96W

9. Field Name: GRAND VALLEY

10. Field Number: 31290

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 01/13/2012 13. Date TD: 01/17/2012 14. Date Casing Set or D&A: 01/18/2012

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 5334 TVD** 5311 17 Plug Back Total Depth MD 5291 TVD** 5268

18. Elevations GR 5064 KB 5088

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL / RPM
SP/GR/HDIL/ZDL/CN and CBL
MUD

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	18	48	0	40	15	0	40	VISU
SURF	13+1/2	9+5/8	32.3	0	555	175	0	555	VISU
1ST	7+7/8	4+1/2	11.6	0	5,323	930	3,140	5,323	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

Details of work: _____

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH	784		<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	2,450		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	4,755		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	5,228		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: the "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

Surface Pressure = 70

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Julie Lawson

Title: Permit Tech II Date: 4/5/2012 Email: julie.lawson@wpenergy.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400268631	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400268633	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400268618	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400268630	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Requested HDIL/GR/SP paper log. Added mud to list of logs run.	6/11/2012 1:16:53 PM

Total: 1 comment(s)