



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600431

Date	03-21-12	Well Owner	Kerr McGee	Well No.	15N-22HZ	Lease	GUBBLER
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME 6)						
City, State Zip	Denver, Colorado 80202					2055938.DRL	
Type of Job			Depth	FL 1024		80012090	
Surface	9 7/8" CSG-36" 13 1/2" HOLE		Bottom of Surface	FL 1014			
Plug			Plug Landed @	972	Ft.	Time On	2200
Production			Pipe Landed @	1014	Ft.	Plug Down	0315

Description	Qty.	Mess.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	750	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	156	Miles		
Fuel Surcharge	156	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	0217	0224
Disp. Rate	5 BPM	Mixing	0224	0257
Slurry Vol.	1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	0257	0300
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0300	0315
Water/Cement	6.25 Gal/SK			
Water Temp.	52°F			
Total Slurry Vol.	176.3	BBLS Cement		
Landed Plug @	1000	PSI/Final Lift @	425	PSI
Pre-Flush W/	30	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/	75.1	BBLS H <sub>2</sub> O	State CO 2.9%	Tax
Circulate	6	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		52			
1214-1216		Bulk Truck		52-52			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JUSTIN, EVAN, STEVE, CHRIS

Received By Jim Foulke  
Customer or His Agent