

FORM  
5Rev  
02/08

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400273914

Date Received:

04/18/2012

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: Julie Lawson

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 260-4533

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-045-20482-00

6. County: GARFIELD

7. Well Name: ExxonMobil

Well Number: GM 522-23

8. Location: QtrQtr: NWSW Section: 23 Township: 6S Range: 96W Meridian: 6

Footage at surface: Distance: 1818 feet Direction: FSL Distance: 861 feet Direction: FWL

As Drilled Latitude: 39.506261 As Drilled Longitude: -108.083078

## GPS Data:

Data of Measurement: 04/13/2011 PDOP Reading: 3.2 GPS Instrument Operator's Name: J. Kirkpatrick

\*\* If directional footage at Top of Prod. Zone Dist.: 2505 feet. Direction: FNL Dist.: 1562 feet. Direction: FWL

Sec: 23 Twp: 6S Rng: 96W

\*\* If directional footage at Bottom Hole Dist.: 2505 feet. Direction: FNL Dist.: 1572 feet. Direction: FWL

Sec: 23 Twp: 6S Rng: 96W

9. Field Name: GRAND VALLEY

10. Field Number: 31290

11. Federal, Indian or State Lease Number: COC34553

12. Spud Date: (when the 1st bit hit the dirt) 09/29/2011 13. Date TD: 10/04/2011 14. Date Casing Set or D&amp;A: 10/05/2011

## 15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7820 TVD\*\* 7680 17 Plug Back Total Depth MD 7770 TVD\*\* 7630

18. Elevations GR 5974 KB 6000

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

CBL, Mud, &amp; RPM

## 20. Casing, Liner and Cement:

## CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	18	48	0	63	23	0	63	VISU
SURF	13+1/2	9+5/8	32.3	0	935	260	0	935	VISU
1ST	7+7/8	4+1/2	11.6	0	7,805	1,010	4,132	7,805	CBL

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH	2,518		<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	4,486		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	7,171		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	7,693		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: the "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

Surface Pressure = 5

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Julie Lawson

Title: Permit Tech II

Date: 4/18/2012

Email: Julie.Lawson@wpenergy.com

**Attachment Check List**

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400273932	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400273935	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400273914	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400273931	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

**General Comments**

User Group	Comment	Comment Date
Permit	Added mud to list of logs run. Requested paper RPM log.	5/8/2012 8:33:18 AM

Total: 1 comment(s)