

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400276019

Date Received:

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐

PluggingBond SuretyID

20010124

3. Name of Operator: KERR-MCGEE OIL &amp; GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: Cheryl Light Phone: (720)929-6461 Fax: (720)929-7461

Email: cheryl.light@anadarko.com

7. Well Name: RAYMOND Well Number: 36N-29HZ

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 11819

## WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 29 Twp: 3N Rng: 66W Meridian: 6

Latitude: 40.202415 Longitude: -104.797090

Footage at Surface: 248 feet FNL/FSL FNL 1536 feet FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4925 13. County: WELD

## 14. GPS Data:

Date of Measurement: 02/21/2012 PDOP Reading: 1.8 Instrument Operator's Name: ROB WILSON

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FNL/FWL  
 620 FNL 2679 FEL 460 FSL 2640 FWL  
 Sec: 29 Twp: 3N Rng: 66W Sec: 29 Twp: 3N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 246 ft

18. Distance to nearest property line: 217 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 16 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		320	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please see attached Oil and Gas Lease.

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 6102

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+1/2	9+5/8	36.0	0	900	430	900	0
1ST	8+3/4	7	26.0	0	7,595	750	7,595	
1ST LINER	6+1/8	4+1/2	11.6	6582	11,819			

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be used/Unit Configuration: W/2E/2, E/2W/2/The surface location of this well is an exception to Rule 318A.a and to Rule 318A.c. This well is not within the GWA surface location window and does not meet the twinning requirement due to the number of wells planned for this area and at the request of the surface owner. An exception location request letter and signed waivers are attached to the Form 2 and Form 2A./Operator will run open hole logs into the surface casing on the first well drilled on this pad/Noble Energy has agreed to comply with the BMPs respecting horizontal well fracturing stimulation. Please see attached BMP Compliance Letter.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Rebecca Heim

Title: Regulatory Analyst II Date: \_\_\_\_\_ Email: DJRegulatory@anadarko.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### Attachment Check List

Att Doc Num	Name
400276021	DEVIATED DRILLING PLAN
400276022	PLAT
400276023	TOPO MAP
400276025	30 DAY NOTICE LETTER
400276026	SURFACE AGRMT/SURETY
400276027	OIL & GAS LEASE
400276028	EXCEPTION LOC REQUEST
400276029	EXCEPTION LOC WAIVERS
400276031	PROPOSED SPACING UNIT
400276032	OTHER
400294464	DIRECTIONAL DATA
400294694	VARIANCE REQUEST

Total Attach: 12 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	<p>"Prior to drilling operations, Operator may perform an anti-collision review of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision review may include MWD or gyro surveys and surface locations of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well may only be drilled if the anti-collision review results indicate that the risk of collision is sufficiently low as defined by the anti-collision plan, with separation factors greater than 1.5, or if the risk of collision has been mitigated through other means including shutting in wells, plugging wells, increased drilling fluid in the event of lost returns or as is appropriate for the specific situation. In the event of an increased risk of collision, that risk will be mitigated to prevent harm to people, the environment or property. For the proposed well, upon conclusion of drilling operations, an as-constructed directional survey will be submitted to COGCC with the Form 5."</p> <p>At the time of permitting; the operator has identified the following well(s) as being within close proximity of the proposed well:</p> <p>RAYMOND 36N-29HZ: - MILLER 21-29 - MILLER L 29-24 - MILLER L 29-24D</p>
Drilling/Completion Operations	Kerr McGee acknowledges and will comply with the COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Total: 2 comment(s)