

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400267661

Date Received:

04/03/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: Julie Lawson

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 260-4533

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-045-20511-00

6. County: GARFIELD

7. Well Name: Bosely

Well Number: SG 313-23

8. Location: QtrQtr: NWSW Section: 23 Township: 7S Range: 96W Meridian: 6

Footage at surface: Distance: 2151 feet Direction: FSL Distance: 1399 feet Direction: FWL

As Drilled Latitude: 39.421773 As Drilled Longitude: -108.082057

GPS Data:

Date of Measurement: 08/30/2011 PDOP Reading: 2.2 GPS Instrument Operator's Name: J. Kirkpatrick

** If directional footage at Top of Prod. Zone Dist.: 2434 feet. Direction: FSL Dist.: 986 feet. Direction: FWL

Sec: 23 Twp: 7S Rng: 96W

** If directional footage at Bottom Hole Dist.: 2417 feet. Direction: FSL Dist.: 981 feet. Direction: FWL

Sec: 23 Twp: 7S Rng: 96W

9. Field Name: GRAND VALLEY

10. Field Number: 31290

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 01/07/2012 13. Date TD: 01/12/2012 14. Date Casing Set or D&A: 01/12/2012

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 5446 TVD** 5407 17 Plug Back Total Depth MD 5010 TVD** 4971

18. Elevations GR 5064 KB 5088

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, MUD, & RPM

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	18	48	0	40	15	0	40	VISU
SURF	13+1/2	9+5/8	32.3	0	583	160	0	583	VISU
1ST	7+7/8	4+1/2	11.6	0	5,435	956	4,250	5,435	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 02/22/2012

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
SQUEEZE	1ST	3,922	650	2,500	4,240

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH	806		<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	2,461		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	4,787		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	5,263		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: the "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

Surface Pressure = 0

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Julie Lawson

Title: Permit Tech II

Date: 4/3/2012

Email: julie.lawson@wpenergy.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400267673	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400267674	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400267661	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400267671	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Added Mud to list of logs run.	6/11/2012 12:33:30 PM

Total: 1 comment(s)