



**CEMENTER'S WELL SERVICE, INC.**  
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

**200169**

Date <b>10/29/2011</b>	Well Owner <b>GREAT WESTERN</b>	Well No. <b>20-54</b>	Lease <b>MANENTI</b>
County <b>WELD</b>	State <b>COLORADO</b>	Field	
Charge to <b>CADE DRILLING, LLC</b>			Charge Code
Address <b>3450 WCR 27 UNIT #2 (CADE# 22)</b>			For Office Use Only
City, State <b>FT. LUTON, COLORADO 80621</b>			
Pump Truck No. <b>1201</b>	Code	Bulk Truck No. <b>1218/1214</b>	Code
Type of Job	Depth	Ft. <b>870</b>	To
Surface <b>8 5/8 CSG 24"</b>	Bottom of Surface	Ft. <b>859</b>	To
Plug	Plug Landed @ <b>817</b>	Ft. Time On <b>1008</b>	
Production	Pipe Landed @ <b>859</b>	Ft. Time Off <b>Rig Down 1200</b>	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat ✓	610	SKS		
	Poz. Mix				
	Calcium Chloride	3970			
	Gel % Flo-Cele 1/4 #Per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement				
8 5/8	GUIDE SHOE	1			
"	CEMENT BASKET	1			
"	CENTRALIZERS	3			
"	BAFFLE PLATE	1			
	BOX THREAD LOCK	1			
	MIXING RATE 4 BPM / DISP RATE 5 BPM				
	SLURRY VOL 118 CU FT / SK - SLURRY WT 14.8-15.0 PPG				
	TOTAL SLURRY VOL 128.1 BBS CEMENT / PLUG LANDED @ 450 PSI				

Remarks: <b>PRE-FLUSH w/ 20 BBS H2O</b>	Tax Reference Code	Sub Total
<b>DISPLACE w/ 52 BBS H2O</b>	State <b>CO 2.9 %</b>	Tax
<b>CIRCULATE 4 BBS CEMENT</b>	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		27			
1214/1218		Bulk Truck		27/27			