

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400277258

Date Received:

05/01/2012

PluggingBond SuretyID

20100017

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
 SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refilling ☐Sidetrack ☐3. Name of Operator: ENCANA OIL & GAS (USA) INC4. COGCC Operator Number: 1001855. Address: 370 17TH ST STE 1700City: DENVER State: CO Zip: 80202-56326. Contact Name: Erin Hochstetler Phone: (720)876-5827 Fax: ()Email: erin.hochstetler@encana.com7. Well Name: N Parachute Well Number: UWF07C-05K04596

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 13000

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 4 Twp: 5S Rng: 96W Meridian: 6Latitude: 39.643300 Longitude: -108.175322

Footage at Surface: 2363 feet FSL 2314 feet FWL
 FNL/FSL FEL/FWL

11. Field Name: Grand Valley Field Number: 3129012. Ground Elevation: 8199.1 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 04/11/2012 PDOP Reading: 1.2 Instrument Operator's Name: Brian Baker15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
1910 FNL 1638 FEL 1910 FNL 1638 FEL
 Sec: 5 Twp: 5S Rng: 96W Sec: 5 Twp: 5S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 3115 ft18. Distance to nearest property line: 2908 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 262 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES			
Williams Fork	WMFK	510-13		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T5S-R96W-Sec. 5: All and other lands. See attached mineral lease map.

25. Distance to Nearest Mineral Lease Line: 1910 ft 26. Total Acres in Lease: 25889

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Recycle and bury

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	20	line pipe	0	120	176	120	0
SURF	14+3/4	9+5/8	36	0	2,200	851	2,200	0
1ST	8+3/4	4+1/2	12	0	13,000	724	13,000	0

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Production casing size of hole will be either 8 3/4 or 7 7/8 and the cement top will be 200' above WMFK.

34. Location ID: 335690

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Erin Hochstetler

Title: Permitting Technician Date: 5/1/2012 Email: erin.hochstetler@encana.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 6/14/2012

API NUMBER

05 045 21529 00

Permit Number: _____ Expiration Date: 6/13/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400277258	FORM 2 SUBMITTED
400278487	WELL LOCATION PLAT
400278488	DEVIATED DRILLING PLAN
400279003	DIRECTIONAL DATA
400279004	MINERAL LEASE MAP

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	No public or LGD comments. Final Review--passed.	6/14/2012 7:53:09 AM
Permit	Proposed BHL not spaced for ILES, but this location meets statewide spacing rules. One of 8 wells on pad evaluating ILES.	6/7/2012 10:55:00 AM
LGD	Passed DB	5/14/2012 4:09:46 PM

Total: 3 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Construction	<ul style="list-style-type: none">• Use solar panels as an alternative energy source for on-location production equipment, where appropriate, economically and technically feasible.• Use multiple gathering lines placed in a single trench to minimize disturbance and construction, where appropriate, economically and technically feasible.• Install trench plugs (sloped to allow wildlife or livestock to exit the trench should they enter) at known wildlife or livestock trails to allow safe crossing on long spans of open trench, where appropriate, economically and technically feasible.• Install pipeline crossings at right angles to the drainages, wetlands, and perennial water bodies, where appropriate, economically and technically feasible.• Limit in-stream construction activity to 24-hours for water bodies less than ten feet wide and to 48-hours for water bodies greater than ten feet wide at locations where horizontal boring is not feasible, where appropriate, economically and technically feasible.• Maintain a minimum of five feet of soil cover between the pipeline and the lowest point of the drainage or water body channel.
Wildlife	<p>Perform biological surveys (on-site) for each new development, using the most recent data sets for wildlife and aquatic resources.</p> <ul style="list-style-type: none">• Perform pre-disturbance surveys when the on-site inspection and commencement of disturbance occur in different field seasons using the most recent data sets for wildlife and aquatic resources.• Utilize the Encana Wildlife Resources Matrix to identify and document (where appropriate) potential impacts or concerns during the project planning phase for proposed drilling operations and construction of roads, pads and pipelines.• Prohibit Encana employees and contractors from carrying projectile weapons on Encana property, except during company organized events.• Prohibit pets on Encana property.• Strategically apply fugitive dust control measures, including enforcing established speed limits on Encana private roads, to reduce fugitive dust and coating of vegetation and deposition in water sources.• Use enclosed, locking garbage receptacles or implement a strict daily trash removal regime on each temporary or permanent work location.

Total: 2 comment(s)