



Hoagland 43-4D
05-123-33883
SESE Sec 4 T3N R68W
Weld County, Colorado
WELLBORE SCHEMATIC
6/15/2012

Spud Date: 5/21/2012
Ensign 55

Rig released: 5-26-2012

Surface Casing:

8 5/8" 24# J-55
Surf to 726'
Cementers Inc. cmt. 5-22-12 w/ 510 sxs,
circ. 6 Bbl. To surf.

Production Casing:

4.5" 11.6# E-80
Surf to 7717', Cmt. w/ Halliburton on 5-26-12
with 320 sxs 11.3# Lead, and
200 sxs FracCemB2 13.5# tail cmt.

Tubing:

not run yet

Workovers:

None Yet

KB: 5029
GL: 5013

TOC: 3300' from Superior CBL
run 5-31-2012

Formation Perfs:

Faced Codell on 6-4-2012 with Halliburton
pumped 800 BBL. Pad and 4133 BBL. SLF Fluid
90,300 lbs. of 30/50 Ottawa Sand
ATP= 3900 psi, Max=4482 psi, AR= 57.9 BPM,
Max= 60.6 BPM, ISIP=2790 psi, FG=0.826, 5 min.= 2693psi

MD: 7725'
TVD: 7534'
PBTD: 7672'

Codell 7531-7554' , 4 spf, 90 phasing

