



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600396

Date	3/19/12	Well Owner	Kerr McGee	Well No.	4C-27 HZ	Lease	Barclay
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Xtreme 8)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	Fl.	905			
Surface	9 5/8" CSG 26" 13 1/2" Hole	Bottom of Surface	Fl.	894			
Plug		Plug Landed @	851	Fl.	Time On 0800		
Production		Pipe Landed @	894	Fl.	Plug Down 1315		

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	670	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	126	Miles		
Fuel Surcharge	126	Miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1213	1219
Disp. Rate	5 BPM	Mixing	1219	1258
Slurry Vol.	1.32 ³ Cu.FL/Sk	Change Valves	1258	1301
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1301	1315
Water/Cement	6.25 Gal/SK			
Water Temp.	62°F			
Total Slurry Vol.	157.5	BBLS Cement		
Landed Plug @	1000	PSI/Final Lift @ 400	PSI	
Pre-Flush W/	20	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace W/	65.7	BBLS H ₂ O	State CO 2.9%	Tax
Circulate	5	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		42			
1219 / 1234		Bulk Truck		42 / 42			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim Adams, JSSA, will

Received By [Signature]

Customer or His Agent