



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600344

Date	2-6-12	Well Owner	Kerr McGee	Well No	29C-2742	Lease	BARCLAY
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME - B)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		FL	899		
Surface	9 5/8" CSC-36 # - 13 1/2" HOLE	Bottom of Surface		FL	889		
Plug		Plug Landed @	849	FL	Time On	1915	
Production		Pipe Landed @	889	FL	Plug Down	0215	

Description	Qty.	Meas.
Set Up Charge	1	
Cement Neat TYPE III	660	SKS
Poz. Mix		
Calcium Chloride	2.5	%
Gel % Flo-Cete 1/4 # Per Sack		
Mileage Charge 2057357	126	Miles
Fuel Surcharge 80017090	126	MILES
Additional Cement		SKS
Mixing Rate 4 BPM	Pre-Flush	0115 - 0120
Disp. Rate 5 BPM	Mixing	0120 - 0159
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	0159 - 0202
Slurry Wt. 14.8 - 15.0 PPG	Displacement	0202 - 0215
Water/Cement 6.25 Gal/SK		
Water Temp. 59°F		
Total Slurry Vol. 155.1	BBSL Cement	
Landed Plug @ 850	PSI/Final Lift @ 400	PSI
Pre-Flush W/ 20	BBSL H ₂ O	Tax Reference Code
Displace W/ 65.6	BBSL H ₂ O	State CO 2.9%
Circulate 6	BBSL Cement	Total

Tool No.

Code

State Mileage

Notes

Comments

Mileage