



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600381

Date	2/22/12	Well Owner	Kerr McGee	Well No.	3N-27H2	Lease	Barckay
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Xtreme 8)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	895		
Surface	95% CSG 35# 13 1/2 H/c	Bottom of Surface		Ft.	889		
Plug		Plug Landed @	846	Ft.	Time On	0500	
Production		Pipe Landed @	889	Ft.	Plug Down	1145	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	660	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge 206/442.0RL	126	Miles		
Fuel Surcharge 800/2090	126	Miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	1046	1050	
Disp. Rate 5 BPM	Mixing	1050	1128	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	1128	1131	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1131	1145	
Water/Cement 6.25 Gal/SK				
Water Temp. 64°F				
Total Slurry Vol. 155.1	BBL'S Cement			
Landed Plug @ 950	PSI/Final Lift @ 400	PSI		
Pre-Flush W/ 20	BBL'S H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 65.3	BBL'S H ₂ O	State CO 2.9%	Tax	
Circulate 4	BBL'S Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		42			
1214/1216		Bulk Truck		42/42			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim Allen, Jason, Josh

Received By Max Allen
Customer or His Agent