

**FORM
5**Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400296630

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: Matt Barber

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 606-4385

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-045-20470-00

6. County: GARFIELD

7. Well Name: ExxonMobil

Well Number: GM 343-22

8. Location: QtrQtr: NWSW Section: 23 Township: 6S Range: 96W Meridian: 6

Footage at surface: Distance: 1832 feet Direction: FSL Distance: 811 feet Direction: FWL

As Drilled Latitude: 39.506300 As Drilled Longitude: -108.083257

GPS Data:

Date of Measurement: 04/13/2011 PDOP Reading: 3.0 GPS Instrument Operator's Name: Jack Kirkpatrick

** If directional footage at Top of Prod. Zone Dist.: 1988 feet. Direction: FSL Dist.: 932 feet. Direction: FEL

Sec: 22 Twp: 6S Rng: 96W

** If directional footage at Bottom Hole Dist.: 1999 feet. Direction: FSL Dist.: 954 feet. Direction: FEL

Sec: 22 Twp: 6S Rng: 96W

9. Field Name: GRAND VALLEY

10. Field Number: 31290

11. Federal, Indian or State Lease Number: COC34553

12. Spud Date: (when the 1st bit hit the dirt) 06/25/2011 13. Date TD: 07/01/2011 14. Date Casing Set or D&A: 07/02/2011

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7923 TVD** 7574 17 Plug Back Total Depth MD 7873 TVD** 7524

18. Elevations GR 6089 KB 6113

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

SP/GR/HDIL/ZDL/CN and CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	18	48	0	80	31	0	80	VISU
SURF	13+1/2	9+5/8	32.3	0	967	260	0	967	VISU
1ST	7+7/8	4+1/2	11.6	0	7,907	995	3,350	7,907	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH	2,675		<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	4,701		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	7,399		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	7,832		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: the "as-drilled" GPS information provided is actual data of the existing well conductor location prior to big rig spud date.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Matt BarberTitle: Sr. Regulatory Specialist Date: _____ Email: matt.barber@wpenergy.com**Attachment Check List**

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400296712	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400296710	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400296682	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
-------------------	----------------	---------------------

--	--	--

Total: 0 comment(s)