



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600339

Date <u>2/4/12</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>15N-26H2</u>	Lease <u>Camp</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (MAJOP #42)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl.	
<u>Surface</u>	<u>9 5/8" CG-36" 13 1/2" Hole</u>	<u>928</u>	
Plug	Bottom of Surface	Fl.	
		<u>918</u>	
Production	Plug Landed @ <u>874</u>	Fl.	Time On <u>1800</u>
	Pipe Landed @ <u>918</u>	Fl.	Plug Down <u>0745</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>Type III 100% Excess</u>	680	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge <u>2003616</u>	126	Miles		
Fuel Surcharge <u>80012090</u>	126	Miles		
Additional Cement	40	SKS		
Mixing Rate 4 BPM	Pre-Flush	0653-0659		
Disp. Rate 5 BPM	Mixing	0659-0729		
Slurry Vol. 1.32 Cu.Ft./Sk	Change Valves	0729-0732		
Slurry Wt. 14.8 - 15.0 PPG	Displacement	0732-0745		
Water/Cement 6.25 Gal/SK				
Water Temp. <u>45°F</u>				
Total Slurry Vol. <u>174</u>	BBLS Cement			
Landed Plug @ <u>600</u>	PSI/Final Lift @ <u>300</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace W/ <u>67.5</u>	BBLS H <sub>2</sub> O	State <u>CO 2.9%</u>	Tax	
Circulate <u>3</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>42</u>			
<u>1217/1218</u>		Bulk Truck		<u>42/42</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Steve, Chris & Fawn

Received By Randy Galt  
Customer or His Agent