

SURFACE USE AGREEMENT AND GRANT OF EASEMENTS

THIS SURFACE USE AGREEMENT AND GRANT OF EASEMENTS ("Agreement") is effective the 19th day of September, 2011, by and between Bord Gulch Ranch, LLC, a Georgia limited liability company, Post Office Box 36, Craig, Colorado 81625 ("Owner") and Axia Energy, LLC, whose address is 1430 Larimer Street, Suite 400, Denver, CO 80202 ("Operator").

RECITALS

A. Owner owns the surface of the real property in Moffat County, Colorado (the "Property"), legally described as:

TOWNSHIP 8 NORTH RANGE 93 WEST OF THE 6TH P.M.

Section 3:	Lots 1, 2, 7, 8, 9, 10, 15, 16
Section 4:	Lots 1, 2, 3, 4, 5, 6, 7, 8
Section 8:	SE1/4, NE1/4NE1/4, S1/2NE1/4, E1/2SW1/4, SE1/4SW1/4
Section 9:	N1/2SW1/4, NW1/4, S1/2SW1/4, SE1/4, NE1/4
Section 10:	NW1/4NE1/4, NE1/4SW1/4, NW1/4NW1/4, S1/2NW1/4, NW1/4SW1/4, S1/2SW1/4, E3/4SE1/4SE1/4
Section 11:	SE1/4SW1/4, W1/2W1/2SW1/4SW1/4
Section 14:	NE1/4NW1/4, W1/2W1/2NW1/4NW1/4, W1/2SW1/4NW1/4, W1/2NW1/4SW1/4, SW1/4SE1/4, S1/2NE1/4, S1/2SE1/4NW1/4, S1/2SW1/4, N1/2NE1/4SW1/4, E1/2SE1/4
Section 15:	SW1/4NE1/4, N1/2SW1/4, SE1/4SW1/4, NW1/4SE1/4, W1/2SW1/4SE1/4, S1/2NW1/4, N1/2NW1/4, SW1/4SW1/4, E3/4NE1/4NE1/4, E1/2SE1/4NE1/4, E1/2NE1/4SE1/4, SE1/4SE1/4
Section 17:	E1/2NW1/4, E1/2, NE1/4SW1/4
Section 21:	Lots 1, 3, NE1/4
Section 22:	NW1/4NW1/4, NE1/4NE1/4
Section 23:	NW1/4NW1/4, NE1/4, E1/2NW1/4
Section 28:	W1/2NW1/4
Section 29:	Lots 1, 5, NE1/4
Section 33:	NE1/4, E1/2SE1/4
Section 34:	W1/2W1/2, NE1/4SW1/4

B. Concurrent with the execution of this agreement Operator and Owner are executing an Oil and Gas Lease (the "lease") covering parts of the Property described above.

C. Operator wishes to drill oil and gas wells ("Wells") with associated necessary pipelines on the Property and also to directionally access adjacent lands pooled with the Property

T.C.

from a surface location of the Property for the extraction of oil, gas and associated hydrocarbons from the Property and said adjacent lands pooled therewith.

TERMS

THEREFORE, in consideration of the mutual covenants in this Agreement, and Operator's agreement to pay the damages described in this Agreement, the parties agree as follows:

1. Wells and Well Pads.

1.1. Operator may construct the necessary well site pads for drilling, completion, re-completion, reworking, re-entry, production, maintenance and operation of Wells ("Well Pad(s)") on the Property consistent with this Agreement. Operator, its agents, employees, assigns, contractors and subcontractors, may enter upon and use the Well Pads for the purposes of drilling, completing, producing, maintaining, and operating Wells to produce oil, gas and associated hydrocarbons produced from the Property or, subject to Owner's consent, adjacent lands, including the construction and use of frac pits, tank batteries, water disposal pits, production equipment, compressor sites and other facilities used to produce and market the oil, gas and associated hydrocarbons.

1.1.1. No Well Pad shall exceed five (5) acres of disturbed area, including any cuts and fills during drilling. After completion operations for the wells on the pad are finished, the size of the Well Pads shall be reduced to a maximum of three (3) acres. Location of Well Pads shall be subject to Section 2.8 of this Agreement.

1.1.2. As allowed by this Agreement, Operator may drill the maximum number of Wells on the Well Pad(s) permitted by Colorado Oil and Gas Conservation Commission ("COGCC") spacing and density requirements. Operator may drill directionally from Well Pads located on the Property to bottom hole locations located directly under the Property. Subject to Owner's consent, which Owner may withhold at its sole discretion, Operator may directionally and/or horizontally drill from Well Pads located on the Property to bottom hole locations located under Surface Acreage that is adjacent to the Property.

1.1.3. As used in this Agreement, "Well" shall mean a well and the accompanying wellbore (either vertically or directionally or horizontally drilled from the Well Pad) for the production of oil and gas, and all associated casing and wellhead equipment.

1.2. As consideration for use by Operator of the surface of the Property, Operator shall pay Owner [REDACTED] for each Well Pad that is constructed on the Property with such payment to be received by Owner prior to commencement of any operations. Provided Operator obtains Owner's verbal permission, Operator shall be allowed to stake and survey the Property and such action shall not be considered as commencement of operations. In addition, prior to the commencement of drilling operations of any well, Operator shall pay Owner [REDACTED] for each

well that is drilled from a Well Pad located on the Property. Such payments shall constitute payment in full by Operator for damages to the Surface associated with ordinary use of the Property for the drilling, construction, completion, re-completion, reworking, reentry, production, operation and maintenance of the Well(s).

1.3. The slope of a Well Pad to any ditch, road, or other improvement shall not be greater than 2:1.

1.4. All above-ground permanent structures on the Well Pad(s) and above-ground pipeline structures shall be painted with appropriate earth-tone colors to blend with the surrounding landscape, and, at the discretion of Operator, shall be screened with appropriate planting as described by the NRCS (National Resource Conservation Services) techniques guide. Operator shall use diligent efforts to minimize disturbances to existing trees and vegetation near the Well Pad.

1.5. Noise levels shall not exceed Colorado Oil and Gas Conservation Commission ("COGCC") regulations.

1.6. All drilling fluids and mud shall be handled in accordance with COGCC regulations. No fluids, mud, soil, or other substances created or derived from operations conducted off of the Property shall be deposited on the surface estate of the Property. Nothing in this section shall limit Operator's right to bring onto the property, use, and reuse frac and production water for additional drilling and completion operations.

1.7. At Owner's request, during drilling operations and thereafter, the Well Pad shall be fenced with five-strand barb wire fencing affixed to sturdy wooden posts spaced six (6) feet apart at a height not less than forty-eight (48) inches.

1.8. To the extent practicable, the Well Pad and any roads or pipelines shall be located to avoid any water wells, irrigation, or tail water ditch or pipes. A plat generally depicting (some but not all) Owners facilities and proposed facilities is attached hereto as Exhibit A. Any irrigation or tail water ditch or pipe located within the Well Pad shall be left intact or rerouted to a location approved by Owner so that the delivery of water on the Property is not disrupted. Operator shall be responsible for any repair and/or maintenance of any irrigation ditch or pipe located within the Well Pad. There are drilled water wells and artesian water wells located on the Property and Owner proposes to drill additional water wells on the Property. Location of Well Pads with respect to all water wells shall be subject to Section 2.8 of this Agreement.

1.9. No debris, slash, or other materials shall be burned on the Property (except for the flaring of gas), nor shall such materials be buried on the Property, without the express written consent of Owner, which may be withheld at Owner's sole discretion.

1.10. If required by COGCC, reserve or drilling pits used on the Property, if any, shall be plastic lined during drilling and completion operations. All plastic lining shall be removed during initial reclamation and not buried in place. Excavated material shall be replaced within

thirty (30) days of finalization of completion operations at the associated Well Pad and the Property reclaimed to substantially its original condition.

1.11. No open pit mining shall be permitted on the Property. The Well Pad shall be maintained in a safe condition and in good order, and shall at all times be kept clean and free from litter and debris. Operator shall utilize electronic field monitor devices or another type of monitoring system standard in the industry on all Wells.

1.12. Compressors. If necessary to facilitate the marketing of natural gas and the associated hydrocarbons into pipelines, a natural gas compressor unit(s) may be located on the Property. Operator will use sound mitigation measures that are reasonable and customary and that result in sound levels that comply with governmental laws and regulations. In the event Operator deems that a compressor station is necessary, Operator shall pay Owner [REDACTED] prior to commencement of construction. If requested by any governmental agency during the permitting process for the compressor unit for Owner comments, Owner will not oppose the action. Location of any compressor shall be subject to Section 2.8 of this Agreement.

2. Road, Pipelines, and Related Issues.

2.1. Road. Owner grants to Operator a non-exclusive access easement ("Road Easement") on the Property for ingress and egress by Operator and its employees, contractors, sub-contractors, agents, and business invitees as needed to conduct oil and gas operations as described in this Agreement. The Road Easement shall be approximately twenty (20) feet in width, being ten (10) feet on each side of the centerline. .

2.1.1. Road construction that requires cuts and fills shall be minimized to the maximum extent possible.

2.1.2. Culverts shall be installed at ditch and drainage crossings when requested by Owner where road cross such ditches or drainages, and shall be sized to prevent obstruction to the free flow of the volumes of water being carried, inclusive of flood stages. Operator shall protect all water sources and conveyance structures, including but not limited to the natural flow of creeks, wells, and ditches, from all operational activities and shall immediately remedy any diversion, curtailment, or blockage of water flows or contamination of water sources.

2.1.3. The road shall at all times be properly graded, drained, graveled, and maintained by Operator from commencement of operations through final reclamation of the Well Pad(s) or termination of this Agreement. Further, Operator shall keep the Road Easement in good order, at all times free from litter and debris.

2.1.4. Permanent gates shall be installed at each point where the road intersects perimeter or cross fences. If Owner or Operator chooses to lock any gate on the road, keys shall be provided to the other party.

2.1.5. Operator shall abide by a 15 m.p.h. speed limit at all times on all roads.

2.1.6. Operator shall use the best available methods, other than hard surfacing, to limit dust. Magnesium chloride shall be applied when requested by Owner, up to a maximum of two (2) times per year.

2.1.7. Location of all roadways shall be subject to Section 2.8 of this Agreement, and Owner shall have the right to relocate any road, provided that such relocation does not impose an undue burden on Operator. Any relocated road shall be of similar utility, and all costs associated with such relocation, other than routine maintenance, shall be at Owner's expense.

2.1.8. The Road Easement conveyed by this Agreement shall not include a right of-use by the public to other lands. Owner reserves the right to use all such roads for any purpose, however, Owner shall not unreasonably interfere with Operator's operations.

2.1.9. Consideration. As consideration for the grant of the Road Easement, prior to commencing any use or construction, Operator shall pay Owner a one-time payment of [REDACTED] per linear foot of Road Easement.

2.1.10. Memorandum of Right-of-Way. Operator shall submit a memorandum of right-of-way with the Mesa County Clerk and Records office that will include a final survey plat. Operator will provide owner with a copy of the recorded document.

ADDITION T.C.

2.2. Pipeline Easement. Owner grants to Operator, its agents, employees, contractors, and subcontractors, a non-exclusive pipeline easement ("Pipeline Easement"), approximately fifteen (15) feet in width along existing roads or disturbances if applicable and/or across the Property to the Well Pad(s), or thirty (30) feet when not adjacent to existing roads or disturbances, the right, from time to time, to lay, construct, reconstruct, replace, renew, operate, maintain, repair, change the size of, and remove pipes and pipelines as well as pigging facilities solely for: 1) transporting oil, gas, petroleum products, water, and any other substances recovered during oil and gas production under this Agreement, whether fluid or solid, any products and derivatives of any of those substances, and any combinations and mixtures of any of those substances, and 2) movement of water. Owner also grants to Operator a license for the use of 15 feet parallel to and adjoining one side of the Pipeline Easement as appropriate for temporary use during the initial installation of the pipelines, which shall terminate upon completion of construction.

2.2.1. Nothing in this subsection 2.2 shall be construed as granting Operator the right to place any facilities on the Property other than the pipeline, related pipeline equipment to be placed in the Pipeline Easement and compression facilities permitted under the terms of this Agreement. Location of all Pipeline Easement and Compressor Facilities shall be subject to Section 2.8 of this Agreement.

T.C.

2.2.2. Consideration. As consideration for the grant of the Pipeline Easement, prior to commencing any use or construction on the Pipeline Easement, Operator shall pay Owner a one-time payment of [REDACTED] per linear foot but only as to that portion of the Pipeline Easement that is not located within the Road Easement. Consideration has been paid pursuant to Section 2.1 of this Agreement for that portion of the Pipeline Easement that is located within the Road Easement.

2.2.3. Memorandum of Pipeline. Easement Operator shall submit a memorandum of pipeline easement with the Mesa County Clerk and Recorders office that will include a final survey plat. Operator will provide owner with a copy of the recorded document.

2.5. Easement Construction.

2.5.1 Operator shall use its best efforts to provide written notice to Owner at least two (2) weeks prior to any construction or installation under this Section 2, with the exception of initial construction which may proceed immediately upon execution of this Agreement.

2.5.2 Operator shall bury all gas pipelines placed within any pipeline easement at a depth not less than thirty six (36) inches, and shall install all such pipelines so that they can be detected using a commonly available metal detector.

2.5.3 Operator shall use its best efforts to immediately repair any roadway crossings and fences on or enclosing the Property that is damaged or temporarily taken down during any construction on or use of any pipeline easement.

2.5.4 Any rocks excavated by Operator that are too large (12" or greater) to be incorporated into fill shall be removed.

2.5.5 Operator shall provide Owner with "as-built" survey of all pipelines after construction. It shall be the Operator's responsibility to record necessary documents in Mesa County, and to provide the Owner with a copy of any recorded documents.

2.5.6 Operator shall not use any pipeline easement as a vehicle access point to lands adjacent to the Property. Unless otherwise agreed to by both parties, no gates shall be installed on any fences on or near the boundary lines of the Property.

2.5.7 During installation of any road or pipeline on the Property, and at all times thereafter, Operator shall minimize disruption of, and interference with, any ranching, agriculture, or other operations conducted on the Property now or in the future. No camping, recreation, hunting, or any other non-pipeline related

activities are permissible at any time on the pipeline or road easements or the Property by Operator.

2.5.8 Within 120 days after installation of any pipeline, or any maintenance or repair of any pipeline that disturbs the surface of the Property, Operator shall restore any affected area to its approximate pre-disturbance topography and re-seed all such areas with appropriate native grasses or alfalfa for ground cover and erosion control as requested by Owner. Operator shall ensure a naturally contoured surface over the pipeline easements.

2.6 Term of Grant. The pipeline and road easements granted herein shall continue until: (i) the termination of this Agreement in accordance with Section 8, or (ii) Operator's written surrender of the easement.

2.7. Evolution of Use. Operator's use of the easements shall be limited according to the terms of this Agreement, and the doctrine of "normal evolution of use" shall not apply to Operator's use of the easements.

2.8. Location of Surface Facilities. No pipelines, pipeline equipment or compression facilities or roadways may be placed on the Property except those required to handle and transport gas to and from the storage facility and to transport substances, including water, utilized in operations thereon. Owner may designate reasonable routes for the construction of roads and pipelines and location of compressor facilities on the premises, and roads and pipelines and compressor facilities installed or constructed thereafter by Operator shall be located in conformance with such designated routes. Such designated routes shall not unreasonably restrict the operations on the Property. In no event shall any Well Pad, new Well, pipeline, valve, compressor, or equipment or other surface facilities of Operator be placed within Five Hundred Feet (500') of house, structure or water well existing at the time of the execution hereof or water well hereafter drilled prior to location of a proposed Well Pad in its vicinity, without the written consent of Owner. Operator shall give Owner thirty (30) days' written notice of any proposed roads, pipeline and/or compressor locations. All roads accessing the facilities shall be closed to public use, but shall be available for use by Owner.

3. Weed Control. Operator shall be responsible for controlling all noxious weeds on all areas of its operations.

3.1. Notification. If Operator locates, or Owner notifies Operator in writing of the location of, noxious weeds on any areas subject to this Section 3, Operator shall implement control procedures before the noxious weeds go to seed.

4. Erosion Control. Operator shall be responsible for controlling all erosion of soils at any Well Pad and easement, and on areas adjacent to the Property that is caused by the activities of Operator or its employees, contractors, sub-contractors, or agents. Such erosion control shall include, without limitation, recontouring, reseeding and re-vegetating such lands and restoring any reservoirs or waterways to their previous quality and capacity. Operator's responsibility for erosion control pursuant to this Section 4 shall be ongoing and shall continue even after

termination of Operator's use of a Well Pad or easement, until (i) such time as Owner provides Operator with a written release of Operator's further obligation to control erosion on the Property, or (ii) one year has passed since the last Well was plugged and abandoned or the termination of the easement, as the case may be.

5. Reclamation.

5.1. Initial Reclamation. Within two (2) years after initial disturbance to a Well Pad, except for areas required for current operations such as roads, the wellhead(s), permanent facilities, water pits, future drilling and completion operations, and room for future workover operations, Operator shall restore all disturbed areas in accordance with this subsection 5.1. Such restoration shall commence immediately following completion of the Wells and establishment of equipment on a Well Pad, the completion of a road, and/or the completion of a pipeline, as the case may be.

5.1.1. Operator shall submit copies of a site-specific reclamation plan along with copies of each approved Application for Permit-to-Drill (Form 2), including any conditions of approval for all Wells on the Property, prior to commencement of construction operations with heavy equipment. All interim and final reclamation goals shall be included in the site-specific reclamation plan.

5.1.2. Operator shall provide Owner with: (i) cut and fill diagrams for construction of the Well Pads, including cross sections and plan views with topographic contours; and (ii) a site map showing the location of wellbores, drilling and completion pits, access roads, soil stockpiles, and the layout of drilling and completion equipment.

5.1.3. Operator shall remove all construction materials, in-fill pits and holes no longer necessary of the operation of the Well(s), and remove compaction from the soil in areas no longer necessary of the operation of the Well(s). The operational Well Pad shall be returned to the approximate original topography and seeded with appropriate native vegetation for ground cover and erosion control. Subsidence in any reclaimed area shall be corrected by adding additional topsoil. Crop lands shall be returned to grass or alfalfa, as requested by Owner, and sagebrush areas shall be planted with native grasses and vegetation that existed prior to disturbance.

5.1.4. A minimum of twelve (12) inches of favorable growth medium shall be reapplied during interim and final reclamation. If this quantity of material is not available, existing soils shall be treated with amendments and fertilizer to create a favorable growth medium.

5.1.5. The Well Pad(s) and easements shall be mulched immediately after seeding with weed-free straw or other type of weed-free mulch. Operator shall be responsible for protecting re-plantings, including fencing to exclude animals.

5.1.6. Additional disturbance of native or previously reclaimed areas shall be minimized. If any subsequent disturbances of surface areas are undertaken at any time, the same reclamation and re-vegetation obligations shall apply. Recontouring shall not be required in areas that have been successfully reclaimed.

5.2. Final Reclamation. Final reclamation shall return the entire site to its original topography and vegetation, and shall be complete and successful within three (3) years after the last Well is plugged and abandoned. However, if at the end of the three (3) year period Operator has not completed a successful reclamation because of events beyond its control, Owner agrees to grant Operator in writing a reasonable extension of time to achieve a successful reclamation. Upon final termination of operations, Owner may request culverts and fencing to be left in place, in which case they shall thereafter belong to Owner.

6. Water. Operator shall have no right to use any water located on the Property for all drilling, completion and Well Pad and road construction, except as expressly agreed in writing by Owner, which consent may be withheld at Owner's sole discretion. The Owner's needs of water for agricultural uses shall in all cases be senior to Operator's needs of water. Operator shall take all necessary steps to prevent its operations from polluting any water well, water spring or other water source located on the Property. As to any Well located within one-half (1/2) mile of a water well on the Property, Operator shall test the water well for volume of flow and water quality, both prior to commencement of drilling operations on the Well and after completion of the Well, to ensure that there has been no damage to the water well.

7. Hunting. Operator will not allow any hunting to be conducted on the Property by its employees and contractors. No firearms will be allowed in any vehicle that is utilized by Operators employees or contractors.

8. Termination. This Agreement shall terminate upon the later of: (i) the expiration or termination of the Lease as extended or renewed; or (ii) upon completion of final reclamation. No termination of this Agreement by Owner, Operator or otherwise shall relieve Operator of any obligation under this Agreement incurred or occurring prior to and through the date of termination, including Operator's liability for or obligation to perform any maintenance, reclamation, mitigation, corrective action, or expenditures required pursuant to common law or any federal, state or local statute, regulation, rule or ordinance. Upon termination of the rights granted under this Agreement, Operator shall execute and deliver to Owner, within thirty (30) days of written demand therefor, a recordable release acknowledging that this Agreement has been terminated. If Operator fails or refuses to deliver that acknowledgment, a written notice by Owner reciting any such failure or refusal and that this Agreement is terminated shall, sixty (60) days after the date of recording of that notice, be conclusive evidence against Operator and all persons claiming under Operator of the termination of this Agreement.

9. General Provisions.

9.1. Consultation. Operator shall consult with Owner regarding all significant operations involving Operator's use of the Property. Consultation shall occur at a minimum at the time of staking and surveying. Operator shall notify Owner at least seven (7) days prior to

beginning any work on the Property involving heavy equipment, including but not limited to drilling, excavating, and cutting roads or laying pipelines.

9.2. Consultation during Lambing and Big Game Hunting Seasons. In addition to Section 9.1 above, prior to commencing operations during lambing season (May 1st through June 15th) and big game hunting season (August 15th through December 1st), Operator and Owner shall agree on access and locations so as to not interfere during lambing season (with only small truck allowed), and to least interfere during big game hunting season. 9.3. Surveys, Plans. Prior to construction, Operator shall provide Owner with COGCC well permits and applications, as well as surveys and plans of the Well Pad site, easements, roads, pipelines and equipment location.

9.4. Liability of Operator. Except for the damages covered by this Agreement, Operator shall be liable for any injury to persons, property, or livestock caused by or incident to the operations of Operator, its agents, employees, contractors, or subcontractors ("Operator Group") on the Property, or any damages due to spills of materials, explosions, or any other harmful activity of Operator. Operator shall indemnify and hold harmless Owner from and against any and all past, present and future liability, damages, costs, expenses, fines, penalties and fees (including without limitation reasonable attorney and consultant fees) incurred by or asserted against Owner arising from or regarding or relating to the Operator Group's use of the Wells, Well Pad(s) or easements or any other rights granted by this Agreement. Such indemnification shall extend to and encompass, but shall not be limited to, all claims, demands, actions or other matters which arise under the common law or other laws designed to protect the environment and public health or welfare including, without limitation, the following laws (as amended) and any regulation promulgated under their authority: Endangered Species Act of 1973 (16 U.S.C. § 1531, *et seq.*); Clean Water Act (33 U.S.C. § 1251, *et seq.*); Clean Air Act (42 U.S.C. § 741, *et seq.*); National Environmental Policy Act (42 U.S.C. § 4321, *et seq.*); Comprehensive Environmental Response, Compensation and Liability Act (42 U.S.C. § 9601, *et seq.*); Solid Waste Disposal Act (42 U.S.C. § 6901, *et seq.*); Toxic Substance Control Act (16 U.S.C. § 2601, *et seq.*); Safe Drinking Water Act (42 U.S.C. § 300f, *et seq.*); Occupational Safety and Health Act (29 U.S.C. § 651, *et seq.*); and any applicable state or local statutes, regulations or ordinances. Operator shall, at Owner's option, defend Owner or reimburse Owner as expenses are incurred for Owner's defense against any claims, demands, actions or other matters, whether brought or asserted by federal, state or local governmental bodies or officials, or by private persons, which are asserted pursuant to or brought under any such laws. All of Operator's obligations stated in this subsection 9.3 shall survive termination of this Agreement.

9.5. Regulations: No part of this Agreement shall be construed to relieve Operator from any or all COGCC or regulations, present and future.

9.6. No Off-Site Substances. Operator shall not store or dispose of on the Property any soil, waste, or other substance generated off of the Property, except water to be used for fracing purposes or disposal services.

9.7. Prohibited Items and Activities. Operator shall not be permitted to have, or allow, firearms, crossbows, pets, alcohol, or illegal drugs on the Property. Personal and/or leisure activities are prohibited. No employees, contractors, subcontractors, agents, guests or invitees of Operator shall reside on the Property overnight, with the exception of personnel deemed critical to Well operations by the Operator.

9.8. Insurance. Operator shall keep its operations insured, or comply with applicable self-insurance laws and regulations, for automobile, liability, and workmen's compensation insurance, and for any damages incurred on the Property.

9.9. Operator Liens. Operator shall, at its sole expense, keep the Property free and clear of all liens and encumbrances resulting from Operator's and its agents' activities on the Property, and shall indemnify and hold harmless Owner from and against any and all liens, claims, demands, costs, and expenses, including, without limitation, attorney fees and court costs, in connection with or arising out of any work done, labor performed, or materials furnished.

9.10. No Warranty of Title. This Agreement is made subject to any and all existing easements, rights-of-way, liens, agreements, burdens, encumbrances, restrictions, and defects in title affecting the Property. Owner does not in any way warrant or guarantee title to the Property.

9.11. Subrogation of Rights. Operator shall have the right to discharge or redeem for Owner, in whole or in part, any mortgage, tax, or other lien on the Property that could jeopardize Operator's rights under this Agreement, in which case Operator shall be subrogated to such rights of the party to whom payment is made for purposes of securing and collecting the amounts paid on behalf of the Owner.

9.12. Waiver. The failure of either party to enforce any of its rights under this Agreement upon any occasion shall not be deemed a waiver of such rights on any subsequent occasion(s). The waiver, either express or implied, by any party of any of the rights, terms or conditions in this Agreement shall not be deemed as or constitute a waiver of any other rights, terms or conditions in this Agreement. Any waiver, in order to be valid and effective, must be in writing.

9.13. Notice. Wherever provision is made in this Agreement for the giving, service, or delivery of any notice, statement, or other instrument, such notice shall be given by: (i) personal delivery, or (ii) United States first class mail, postage prepaid, addressed to the party entitled to receive the same at the address stated in the introductory paragraph; provided, however, that each party may change that party's mailing address by giving to the other party written notice of change of such address in the manner provided in this subsection. Mail shall be deemed to have been given, served and delivered upon the third delivery day following the date of the mailing; personal delivery shall be deemed to have been given, served and delivered upon receipt.

9.14. COGCC Notices.

9.14.1. Owner shall be provided with a copy of any "Change of Operator" notice filed with the COGCC pursuant to Rule 312.

9.14.2. A copy of any notice filed with the COGCC regarding public health, safety, or emergency matters shall be delivered to Owner simultaneously with the COGCC notice. In the event of a spill of E&P waste or any substance, Operator shall immediately notify Owner, verbally or by telephone if possible, and identify the quantity, location, and type of substance released. In the event of a surface or subsurface loss of well control, Operator shall notify Owner, verbally or by telephone if possible, as soon as possible. Any verbal or telephonic notification under this subsection shall be documented in writing and provided to Owner in accordance with subsection 9.14.

9.14.3. Copies of all forms, notices, plans, tests, or other documentation regarding spills or blow-outs shall be provided to Owner at the same time as filing with the COGCC, local government representative, or any other regulatory agency.

9.14.4. A copy of any Operator requests for variance from surface use or reclamation regulations, not requiring a petition and notice to Owner, shall be delivered to Owner at the same time as delivery to the COGCC.

9.15. Authority. Operator represents and warrants that it has full authority to commit to this Agreement. Operator shall provide Owner with a copy of all leases, including pooling or communitization agreements, and spacing orders, under which it is operating on the Property.

9.16. Survival of Obligations. All obligations, indemnifications, duties, and liabilities undertaken by Operator under this Agreement shall survive the termination of this Agreement.

9.17. Merger of Prior Agreements. This Agreement and the Lease contain the sole and entire agreement and understanding of the parties with respect to the entire subject matter on the Property. All prior discussions, negotiations, commitments, agreements, and understandings relating to the subjects of this Agreement on the Property, and the Lease are merged into them. In the event of any conflict between the terms of this Agreement and the Lease, the terms of this Agreement shall control.

9.18. Amendments. This Agreement may only be amended by the written agreement of both parties. This Agreement cannot be amended or terminated orally.

9.19. Assignment. This Agreement is assignable by the parties.

9.20. Headings. Section headings or captions contained in this Agreement are inserted only as a matter of convenience and for reference, and in no way define, limit, extend, or describe the scope of this Agreement or the intent of any provision.

9.21. Construction. Whenever required by the context of this Agreement, the singular shall include the plural, and vice versa; and the masculine gender shall include the feminine and neuter genders, and vice versa. The provisions of this Agreement have been independently,

separately and freely negotiated by the parties as if drafted by both of them. The parties waive any statutory or common law presumption that would serve to have this Agreement construed in favor of or against either party.

9.22. Severability. If any provision of this Agreement is illegal, invalid, or unenforceable under present or future laws applicable to this Agreement, the parties intend that the remainder of this Agreement shall remain in full force and effect so as to fulfill as fully as possible the intent of the parties as expressed by the then existing terms of the Agreement, including the invalidated provision.

9.23. Applicable Law and Attorney Fees. This Agreement and the rights of the parties under it shall be governed by and interpreted in accordance with the laws of the State of Colorado, by the District Court of Mesa County, Colorado. In the event of a dispute involving or related to any term or condition of this Agreement, the non-breaching party shall be entitled to recover its reasonable costs and attorney fees, including post-judgment collection costs, in addition to actual damages.

9.24. Heirs, Successors and Assigns. Subject to any limitations on assignment provided in this Agreement, this Agreement shall run with the land and be binding upon and inure to the benefit of the parties and their respective heirs, successors and assigns.

Owner:

BORD GULCH RANCH, LLC

BY: [Signature]
THOMAS GILLILAND (Manager)

STATE OF COLORADO)

COUNTY OF MOFFAT) ss

The foregoing instrument was subscribed and sworn to before me on the 21st day of September 2011, by Thomas Gilliland, as Manager of Bord Gulch Ranch, LLC.

Witness my hand and seal.

My Commission Expires:

9/27/2014


[Signature]
NOTARY PUBLIC

Operator:

AXIA ENERGY, LLC

BY:

[Signature]
TAB MCGINLEY
Vice President of Land



STATE OF COLORADO)


COUNTY OF Denver)

) ss

The foregoing instrument was subscribed and sworn to before me on the 19th day of September, 2011, by Tab McGinley, Vice President of Land for Axia Energy, LLC.

Witness my hand and seal.

My Commission Expires:



Marci A. Winston
NOTARY PUBLIC

My Commission Expires

7/6/13