

FORM
5A

Rev
06/12

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400298339

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100322
2. Name of Operator: NOBLE ENERGY INC
3. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
4. Contact Name: Andrea Rawson
Phone: (303) 228-4253
Fax: (303) 228-4286

5. API Number 05-123-26127-00
6. County: WELD
7. Well Name: BASHOR STATE AA
Well Number: 16-13
8. Location: QtrQtr: SWSW Section: 16 Township: 6N Range: 63W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA-CODELL Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 10/25/2011 End Date: 10/25/2011 Date of First Production this formation: 10/25/2011

Perforations Top: 6750 Bottom: 6760 No. Holes: 40 Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☐

Re-Frac'd Codell w/ 140969 gals of Slick Water and Vistar with 245980#'s of Ottawa sand.

This formation is commingled with another formation: ☒ Yes ☐ No

Total fluid used in treatment (bbl): 3356 Max pressure during treatment (psi): 4726

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal):

Type of gas used in treatment: Number of staged intervals: 6

Total acid used in treatment (bbl): Max frac gradient (psi/ft): 0.46

Recycled water used in treatment (bbl): Flowback volume recovered (bbl):

Fresh water used in treatment (bbl): Disposition method for flowback: RECYCLE

Total proppant used (lbs): 245980 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 12/01/2011 Hours: 24 Bbl oil: 72 Mcf Gas: 360 Bbl H2O: 24

Calculated 24 hour rate: Bbl oil: 72 Mcf Gas: 360 Bbl H2O: 24 GOR: 5000

Test Method: Flowing Casing PSI: 1029 Tubing PSI: 936 Choke Size: 48

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1266 API Gravity Oil: 51

Tubing Size: 2 + 3/8 Tubing Setting Depth: 6735 Tbg setting date: 10/27/2011 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

Bridge Plug Depth: Sacks cement on top:

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Andrea Rawson

Title: Regulatory Specialist Date: _____ Email arawson@nobleenergyinc.com
:

Attachment Check List

Att Doc Num	Name
400298343	WELLBORE DIAGRAM

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)