

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400293833

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

20120018

3. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY LLC

4. COGCC Operator Number: 8960

5. Address: P O BOX 21974

City: BAKERSFIELD State: CA Zip: 93390

6. Contact Name: Keith Caplan Phone: (720)440-6100 Fax: (720)279-2331  
Email: kcapan@bonanzacrk.com

7. Well Name: Antelope Well Number: 11-14-18HZ

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 11110

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 18 Twp: 5N Rng: 62W Meridian: 6

Latitude: 40.404930 Longitude: -104.371170

Footage at Surface: 625 feet FNL/FSL 1178 feet FEL/FWL FNL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4533 13. County: WELD

14. GPS Data:

Date of Measurement: 05/31/2012 PDOP Reading: 1.6 Instrument Operator's Name: Wyatt Hall

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 460 FNL 1000 FWL 460 FSL 1100 FWL 460  
Sec: 18 Twp: 5N Rng: 62W Sec: 18 Twp: 5N Rng: 62W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 462 ft

18. Distance to nearest property line: 625 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 292 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		320	W2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Sec 18: W2, SE/4 plus acreage in other lands

25. Distance to Nearest Mineral Lease Line: 460 ft

26. Total Acres in Lease: 8438

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+1/2	9+5/8	36	0	410	200	410	0
1ST	8+3/4	7+0/0	26	0	6,710	500	6,710	0
1ST LINER	6+1/8	4+1/2	11.6	6610	11,110			

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used. Operator requests an exception location per rule 318Aa and rule 318Ac. Waviers attached. Per rule 318Ae, the Operator requests the proposed spacing unit consisting of 320 acres, W2 of Sec 18 T5N R62W. Proposed spacing unit map and 30-day certificate is attached.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Keith Caplan

Title: Sr. Regulatory Specialist Date: \_\_\_\_\_ Email: kcaplan@bonanzacrk.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

#### API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### **Attachment Check List**

Att Doc Num	Name
400293900	WELL LOCATION PLAT
400299054	SURFACE AGRMT/SURETY
400299055	PROPOSED SPACING UNIT
400299057	EXCEPTION LOC WAIVERS
400299058	WAIVERS
400299059	DEVIATED DRILLING PLAN
400299060	DIRECTIONAL DATA
400299061	EXCEPTION LOC REQUEST

Total Attach: 8 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>

Total: 0 comment(s)

## BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	<p>Wellbore Fracturing Stimulation</p> <p>The Colorado Oil and Gas Conservation Commission (COGCC) has established this Policy Regarding Bradenhead Monitoring During Hydraulic Fracturing Treatments ("Treatment") in the Greater Wattenberg Area ("GWA") pursuant to COGCC 207.a. ("Policy"). This Policy applies to oil and gas operations in the GWA as defined by the COGCC Rules of Practice and Procedure.</p> <p>1. At least twenty (20) days prior to initiating a Treatment, the operator ("Operator") shall provide written notice, via hand delivery, via confirmed receipt email, or via certified mail, return-receipt requested, to all adjacent operators ("Adjacent Operators") where the Adjacent Operator's wellbore is located within 300 feet of the Operator's wellbore and the Adjacent Operator's wellbore penetrates the productive zone which is to be treated by the Operator. Such notice shall include the anticipated date of the Treatment and shall provide a copy of this Policy.</p> <p>2. Within seven (7) days of receipt of such notice, the Adjacent Operator shall confirm in writing to the Operator that it will comply with this Policy. If the Adjacent Operator refuses to confirm that it will comply with this Policy, or fails to timely respond to the Operator's notice, the Operator shall advise the Commission staff of such refusal or failure by email. The Commission may then order the Adjacent Operator's compliance.</p> <p>3. The Operator shall monitor the bradenhead pressure of all wells under Operator's control within 300 feet of the well which is to be treated, provided such other wells penetrate the productive zone which is to be treated.</p> <p>4. The Operator and Adjacent Operator(s) shall install bradenhead pressure gauges on their respective wells 24 hours prior to the Operator initiating a Treatment. The Operator and Adjacent Operator(s) shall monitor their respective gauges at least once during every 24-hour period until 24 hours after the Treatment is completed and shall continue to do so until the pressure stabilizes. The bradenhead pressure gauges shall be capable of monitoring current pressure and also capable of recording the maximum pressure encountered in a 24 hour period. Such gauges shall be reset between each 24 hour period. The pressures shall be recorded and saved for a period of one year. Alternate electronic measurement may be used to record the prescribed pressures.</p> <p>5. If at any time during the Treatment or the 24-hour post-stimulation period, the bradenhead annulus pressure of the Treatment well or any offset wells subject to this Policy increases by more than 200 psig, the Operator of the well being treated, or the Adjacent Operator(s) of an affected offsetting well, as the case may be, shall verbally notify each other and the Director, as soon as practicable, but no later than twenty-four (24) hours following such incident. Within fifteen (15) days after the occurrence, the Operator or Adjacent Operator(s), as the case may be, shall submit a Sundry Notice, Form 4, giving all details, including corrective actions taken.</p>
Drilling/Completion Operations	<p>The operator will comply with the COGCC's bradenhead monitoring policy updated 5/29/2012.</p>

Total: 2 comment(s)