

FORM 5A Rev 06/12

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Table with columns DE, ET, OE, ES

Document Number: 400299538

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120 4. Contact Name: JOEL MALEFYT
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6828
3. Address: P O BOX 173779 City: DENVER State: CO Zip: 80217- Fax: (720) 929-7828

5. API Number 05-123-34454-00 6. County: WELD
7. Well Name: BARCLAY Well Number: 4N-27HZ
8. Location: QtrQtr: SWSW Section: 27 Township: 3N Range: 66W Meridian: 6
9. Field Name: Field Code:

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 05/09/2012 End Date: 05/10/2012 Date of First Production this formation: 05/23/2012

Perforations Top: 7676 Bottom: 11656 No. Holes: Hole size:

Provide a brief summary of the formation treatment: Open Hole: [X]

FRAC'D THROUGH AN OPEN HOLE LINER FROM 7676-11656. AVERAGE TREATING PRESSURE 4433, AVERAGE RATE 58. SAND: 974122 LBS OF 40/70, 1960045 LBS OF 30/50, 128865 LBS OF SB EXCEL FOR A TOTAL WEIGHT OF 3063032 LBS.

This formation is commingled with another formation: [] Yes [X] No

Total fluid used in treatment (bbl): 70526 Max pressure during treatment (psi): 7277
Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.30
Type of gas used in treatment: Number of staged intervals: 19
Total acid used in treatment (bbl): Max frac gradient (psi/ft):
Recycled water used in treatment (bbl): Flowback volume recovered (bbl):
Fresh water used in treatment (bbl): 40333 Disposition method for flowback: DISPOSAL
Total proppant used (lbs): 3063032 Rule 805 green completion techniques were utilized: [X]

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 06/05/2012 Hours: 24 Bbl oil: 250 Mcf Gas: 960 Bbl H2O: 0
Calculated 24 hour rate: Bbl oil: 250 Mcf Gas: 960 Bbl H2O: 0 GOR: 3840
Test Method: FLOWING Casing PSI: 2117 Tubing PSI: 1260 Choke Size: 16/64
Gas Disposition: SOLD Gas Type: WET Btu Gas: 1276 API Gravity Oil: 51
Tubing Size: 2 + 3/8 Tubing Setting Depth: 7144 Tbg setting date: 05/26/2012 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: [] Yes [] No If yes, number of sacks cmt

Bridge Plug Depth: Sacks cement on top:

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JOEL MALEFYT
Title: REGULATORY ANALYST Date: _____ Email: JOEL.MALEFYT@ANADARKO.COM
:

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)