

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400299370

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

20000063

3. Name of Operator: MULL DRILLING COMPANY INC

4. COGCC Operator Number: 61250

5. Address: 1700 N WATERFRONT PKWY B#1200

City: WICHITA State: KS Zip: 67206-6637

6. Contact Name: MARK SHREVE Phone: (316)264-6366 Fax: (316)264-6440

Email: MSHREVE@MULLDRILLING.COM

7. Well Name: SAT UNIT Well Number: 1-14

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 5000

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 14 Twp: 17S Rng: 45W Meridian: 6

Latitude: 38.573580 Longitude: -102.434710

Footage at Surface: 1251 feet FNL/FSL 171 feet FEL/FWL 171 feet

11. Field Name: WILDCAT Field Number: 99999

12. Ground Elevation: 4101 13. County: KIOWA

14. GPS Data:

Date of Measurement: 06/15/2012 PDOP Reading: 3.1 Instrument Operator's Name: KEITH WESTFALL

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 150 ft

18. Distance to nearest property line: 171 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1879 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
MARMATON	MRTN			
MISSISSIPPIAN	MSSP			
MORROW	MRRW			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

SW/4 SECTION 14, E/2 SECTION 15, NE/4 SECTION 21, ALL SECTION 23 AND NW/4 SECTION 27-T17S-R45W, 6TH P.M.

25. Distance to Nearest Mineral Lease Line: 1251 ft 26. Total Acres in Lease: 1440

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☒ Yes ☐ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: DRY BURY

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	300	200	300	0
1ST	7+7/8	5+1/2	15.5	0	5,000	250	5,000	3,500
			Stage Tool	0	2,300	300	2,300	0

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments NO CONDUCTOR OR INTERMEDIATE CASING WILL BE SET.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MARK SHREVE

Title: PRESIDENT/COO Date: _____ Email: MSHREVE@MULLDRILLING.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400299527	H2S CONTINGENCY PLAN
400299528	PLAT
400299529	TOPO MAP
400299619	30 DAY NOTICE LETTER

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Storm Water/Erosion Control	<ul style="list-style-type: none"> • During drilling / completion operations, implementation of Storm Water Pollution Prevention Plan • Following drilling/completion operations, prompt reclamation of disturbed areas • During production operations, implementation of MDC's Post Construction Storm Water Management Program
Final Reclamation	<ul style="list-style-type: none"> • All equipment and debris removed • All remaining disturbed areas, including access roads, reclaimed • Noxious Weed Control Plan developed if appropriate
Planning	PLANNING <ul style="list-style-type: none"> • Conduct Initial Site Assessment <ul style="list-style-type: none"> o Identification of nearby water bodies o Identification of vegetation types o Identification of protected wildlife species o Identification of potential access routes to minimize disturbances o Identification of nearby improvements
Interim Reclamation	<ul style="list-style-type: none"> • Debris and waste material removed • Areas not in use reclaimed promptly; pits closed using segregated material; well pad and other compacted surfaces ripped • Noxious weeds controlled
Site Specific	Reporting of the presence of H2S will be done via verbal and email notices. Verbal notice with a follow up email will be provided as soon as practicable upon detection of H2S to COGCC's area engineer and the local government designee.
Material Handling and Spill Prevention	<ul style="list-style-type: none"> • During drilling/completion operations, storage areas graded towards pit • During production operations, implementation of Spill Prevention, Control and Countermeasure Plan & daily inspection • All stock and produced water tanks have secondary containment
General Housekeeping	<ul style="list-style-type: none"> • Drilling and production operations conducted in safe, workmanlike manner. Safety expectations include good housekeeping. • During drilling/completion operations, debris stored in caged container which is removed from the site. • During production operations, the lease is inspected daily by MDC personnel.
Construction	<ul style="list-style-type: none"> • Access road, well pad and pit disturbances minimized • Soils segregated by type to facilitate reclamation • Storm water controls deployed and routinely inspected

Drilling/Completion Operations	<p>Includes Structural Practices:</p> <ul style="list-style-type: none"> • Implement Storm Water Pollution Prevention Plan, including routine inspections and evaluation of effectiveness • Locate tank batteries at safe distance from public roadways and railhead • Full containment for stock tanks and separators • Installation of pipelines in common trenches when practical • Installation of pipelines at right angles to water bodies (drainages, wetlands, perennial water bodies) where practical
Pre-Construction	<ul style="list-style-type: none"> • Preparation of a Storm Water Pollution Prevention Plan. Acquisition of a Storm Water Discharge Permit • Consultation with the surface landowner or appointed agent • Finalize access routes • Finalize well pad location to minimize surface grade impacts • Finalize well pad layout to minimize disturbances • Develop wildlife management plan if protected species are present
Wildlife	<ul style="list-style-type: none"> • Development and implementation of a Wildlife Management Plan if protected species are present

Total: 11 comment(s)