

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400285178

Date Received:

05/16/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100185

4. Contact Name: Marina Ayala

2. Name of Operator: ENCANA OIL & GAS (USA) INC

Phone: (720) 876-5905

3. Address: 370 17TH ST STE 1700

Fax: (720) 876-4905

City: DENVER State: CO Zip: 80202-

5. API Number 05-045-20214-00

6. County: GARFIELD

7. Well Name: Federal

Well Number: 28-6BB (PL28)

8. Location: QtrQtr: NWSW Section: 28 Township: 7S Range: 95W Meridian: 6

Footage at surface: Distance: 2132 feet Direction: FSL Distance: 766 feet Direction: FWL

As Drilled Latitude: 39.407011 As Drilled Longitude: -108.008896

GPS Data:

Data of Measurement: 09/23/2011 PDOP Reading: 2.1 GPS Instrument Operator's Name: Brandon Birdsall

** If directional footage at Top of Prod. Zone Dist.: 2860 feet. Direction: FNL Dist.: 1974 feet. Direction: FWL

Sec: 28 Twp: 7S Rng: 95W

** If directional footage at Bottom Hole Dist.: 2851 feet. Direction: FNL Dist.: 1989 feet. Direction: FWL

Sec: 28 Twp: 7S Rng: 95W

9. Field Name: PARACHUTE

10. Field Number: 67350

11. Federal, Indian or State Lease Number: COC011523

12. Spud Date: (when the 1st bit hit the dirt) 10/15/2011 13. Date TD: 10/26/2011 14. Date Casing Set or D&A: 10/27/2011

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8190 TVD** 8004 17 Plug Back Total Depth MD 8056 TVD** 7870

18. Elevations GR 7161 KB 7183

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

RST, IBC and Mud.

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42	0	40	40	0	40	CALC
SURF	12+3/4	9+5/8	36	0	1,256	409	0	1,280	CALC
1ST	8+3/4	4+1/2	11.6	0	8,112	638	2,530	8,190	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
MESAVERDE	5,136	5,842	<input type="checkbox"/>	<input type="checkbox"/>	
WILLIAMS FORK	5,843	8,013	<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	8,014	8,190	<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Marina Ayala

Title: Permitting Technician Date: 5/16/2012 Email: marina.ayala@encana.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400285185	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400285183	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400285178	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400285184	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400285186	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400285216	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400285221	LAS-NEUTRON	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)