



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199724

Date 6-27-11	Well Owner Kerr McGee	Well No. 1-32	Lease Fehr
County Weld	State Colorado		
Charge to Kerr McGee Oil & Gas Onshore, LP			
Address 1999 Broadway, Suite 3700	(Xtreme #6)		
City, State Zip Denver, Colorado 80202			
Type of Job	Depth	Ft. 953	
<u>Surface</u> 8 5/8" CSG-24"	Bottom of Surface	Ft. 944	
Plug	Plug Landed @ 900	Ft. Time On 08:15	
Production	Pipe Landed @ 944	Ft. Plug Down 10:30	

Description			Qty.	Meas.	Unit Price	Amount	
Set Up Charge			1				
Cement Neat ✓ Type III			590	SKS			
Poz. Mix							
Calcium Chloride			2.5	%			
Gel % Fio-Cete 1/4 # Per Sack							
Mileage Charge 205273024			186	Miles			
Fuel Surcharge 80012090			186	miles			
Additional Cement				SKS			
Mixing Rate	4 BPM	Pre-Flush	0944	0950			
Disp. Rate	5 BPM	Mixing	0950	1016			
Slurry Vol.	1.32³ Cu.Ft./Sk	Change Valves	1016	1019			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1019	1030			
Water/Cement 6.25 Gal/SK							
Water Temp. 66°F							
Total Slurry Vol. 138.5 BBLS Cement							
Landed Plug @ 350		PSI/Final Lift @ 200	PSI				
Pre-Flush W/ 30		BBLS H²O	Tax Reference Code		Sub Total		
Displace W/ 57.2		BBLS H²O	State CO 2.9%		Tax		
Circulate 4		BBLS Cement	Total				
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		62			
1214/1216		Bulk Truck		62/62			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Justin, Danks, Justin, Dentrio**

Received By **Mac Harkness**

Customer or His Agent