

Kubeczko, Dave

From: Kubeczko, Dave
Sent: Wednesday, June 27, 2012 2:05 PM
To: Kubeczko, Dave
Subject: FW: Quicksilver Pirtlaw Partners, LTD 32-09

Categories: Orange - Operator Correspondence, Dark Green - CDOW Pass

Scan No 2034418

CPW CORRESPONDENCE and PROPOSED BMPs

2A#400262066

From: Cindy Keister [<mailto:ckeister@qrinc.com>]

Sent: Wednesday, May 02, 2012 4:54 PM

To: Davidson, Jacob

Cc: 'joans@romick.com'; 'brent@romick.com'; 'mfiggs@indra.com'; Stan Page; Kubeczko, Dave; Haskins, James; Warren, Michael

Subject: Re: Quicksilver Pirtlaw Partners, LTD 32-09

Quicksilver agrees to the following BMP's.

Cindy Keister

Sent via Blackberry

(682) 429-3861

From: Davidson, Jacob [<mailto:Jacob.Davidson@state.co.us>]

Sent: Wednesday, May 02, 2012 05:30 PM

To: Cindy Keister

Cc: Haskins, James <jim.haskins@state.co.us>; Warren, Michael <Michael.Warren@state.co.us>; Kubeczko, Dave <Dave.Kubeczko@state.co.us>

Subject: Quicksilver Pirtlaw Partners, LTD 32-09

Hello Cindy,

I have gathered field notes from those present at the onsite to generate the following BMPs that CPW recommends for the Pirtlaw Partners LTD, 32-09 well site.

Pad Location: Pirtlaw Partners, LTD 32-09 Located in Section 9, T 6N, R 87W at 40.496215, -107.152379

Document #: 400262066

Wildlife concern: Location is within mapped Columbian sharp-tailed grouse production area, and active bald eagle winter roost site.

Recommended BMPs:

1. Where oil and gas activities must occur near active bald eagle winter roost sites, conduct these activities outside the time period from November 15 through February 28.
2. Restrict post-development well site visitations to between the hours of 10:00 a.m. and 2:00 p.m. from November 15 to March 15 for active bald eagle winter roost sites.
3. Where oil and gas activities must occur within 1.25 miles of Columbian sharp-tailed grouse leks or within other mapped Columbian sharp-tailed grouse breeding or summer habitat, conduct these activities outside the period between March 15 and July 30. Pirtlaw Partners 32-09 is approximately 0.6 miles from the Wolf Mountain Ranch Lek.
4. For work-over activity attempt to avoid March 15 to July 30 time period. If it is necessary to work within that time period consult/notify local CPW contact and restrict daily visits to period from 9am to 4pm.

5. Restrict well site visitations to portions of the day between 9:00 a.m. and 4:00 p.m. during the Columbian sharp-tailed grouse lekking season, from March 15 to June 1.
6. When compressor stations must be sited within 1.25 miles of Columbian sharp-tailed grouse active and inactive (within last 10 years) lek sites, locate compressor stations no closer than 2,500 feet from the lek.
7. Install raptor perch deterrents on equipment, fences, cross arms and pole tops in Columbian sharp-tailed grouse habitat.
8. Reclaim/restore Columbian sharp-tailed grouse habitats with native grasses and forbs conducive to optimal Columbian sharp-tailed grouse habitat and other wildlife appropriate to the ecological site. Reclamation of breeding habitat should include a substantially higher percentage of forbs than other areas.
9. Muffle sound from compressors, pump jacks or other motors necessary to run operations at the site. If mufflers are used, point upward to dissipate sound and vibration.
10. Install and utilize bear-proof dumpsters and trash receptacles for all food-related trash on location following COGCC Rule 1204 a-1.

CPW would appreciate your concurrence with the proposed BMPs, and can have these comments entered into eForms within minutes today.

Thank you,

Jacob Davidson

Land Use Specialist
Colorado Parks and Wildlife
Meeker, Colorado
Jacob.Davidson@state.co.us
Office: (970) 878-6069
Cell: (970) 756-5226