

**FORM
5**Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400300384

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: Angela Neifert-Kraiser

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 606-4398

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-045-20702-00

6. County: GARFIELD

7. Well Name: Jolley

Well Number: KP 41-28

8. Location: QtrQtr: NENE Section: 28 Township: 6S Range: 91W Meridian: 6

Footage at surface: Distance: 303 feet Direction: FNL Distance: 534 feet Direction: FEL

As Drilled Latitude: 39.505595 As Drilled Longitude: -107.551590

GPS Data:

Data of Measurement: 07/28/2011 PDOP Reading: 1.9 GPS Instrument Operator's Name: Jack Kirkpatrick

** If directional footage at Top of Prod. Zone Dist.: 137 feet. Direction: FNL Dist.: 738 feet. Direction: FEL

Sec: 28 Twp: 6s Rng: 91w

** If directional footage at Bottom Hole Dist.: 129 feet. Direction: FNL Dist.: 749 feet. Direction: FEL

Sec: 28 Twp: 6s Rng: 91w

9. Field Name: MAMM CREEK

10. Field Number: 52500

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 11/05/2011 13. Date TD: 11/13/2011 14. Date Casing Set or D&A: 11/15/2011

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8304 TVD** 8295 17 Plug Back Total Depth MD 8225 TVD** 8216

18. Elevations GR 7060 KB 7083

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

SP/GR/HDIL/ZDL/CN/CBL/Mud, and Reservoir Performance Monitor (RPM)

Please note: the "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

*All flowback water entries are total estimates based on comingled volumes.

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	18	48	0	108	39	0	108	VISU
SURF	13+1/2	9+5/8	32.3	0	1,370	561	0	1,370	VISU
1ST	7+7/8	4+1/2	11.6	0	8,271	1,295	3,326	8,271	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work: _____

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
MESAVERDE	4,434		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	7,767		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	8,041		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: the "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

*All flowback water entries are total estimates based on comingled volumes.

SISP 0

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Angela Neifert-Kraiser

Title: Regulatory Specialist

Date: _____

Email: Angela.Neifert-Kraiser@WPXEnergy.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400300423	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400300424	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400300422	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400300513	WELLBORE DIAGRAM	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)