

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400284817

Date Received:

06/01/2012

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒Refilling ☒Sidetrack ☐

PluggingBond SuretyID

20040071

3. Name of Operator: ANTERO RESOURCES PICEANCE CORPORATION4. COGCC Operator Number: 100795. Address: 1625 17TH ST STE 300City: DENVER State: CO Zip: 802026. Contact Name: Shauna Redican Phone: (303)357-6820 Fax: (303)357-7315Email: sredican@anteroresources.com7. Well Name: River Ranch Well Number: B11

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 9012

WELL LOCATION INFORMATION

10. QtrQtr: Lot 7 Sec: 8 Twp: 6S Rng: 92W Meridian: 6Latitude: 39.543590 Longitude: -107.695327Footage at Surface: 1757 feet FNL 1372 feet FWL11. Field Name: Mamm Creek Field Number: 5250012. Ground Elevation: 5382 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 09/07/2006 PDOP Reading: 1.8 Instrument Operator's Name: Samuel D. Phelps15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
2392 FNL 1957 FWL 2392 FNL 1957 FWL
Sec: 8 Twp: 6S Rng: 92W Sec: 8 Twp: 6S Rng: 92W16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 880 ft18. Distance to nearest property line: 1035 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 258 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	191-25		
Williams Fork	WMFK	510-16		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See previously submitted Exhibit A: Portions of the NW/4SE/4, N/2SW/4, S/2/NW/4 and portions of the N/2NW/4 of Section 8 T6S, R92W

25. Distance to Nearest Mineral Lease Line: 689 ft 26. Total Acres in Lease: 233

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Bury onsite if meets Table

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	55#	0	60	177	60	0
SURF	12+1/4	8+5/8	24/32#	0	1,000	416	1,000	0
1ST	7+7/8	4+1/2	11.6#	0	9,012	763	9,012	

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments I certify that all conditions in the original permit are the same except the updated casing and cement program. There have been no other changes to land use, well construction or the lease. This Refile Form 2 does not require a Form 2A because the pad has been constructed, a closed loop system is being used so no pits need to be constructed, the refiled well will not require any expansion / additional surface disturbance of the pad. The location is not in a wildlife restricted surface occupancy area (RSO); consultation with CDOW is not required and the location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii).; consultation with CDPHE is not required.#31 Mud Disposal: Antero will bury onsite if disposal meets Table 910 and if there is a provision in SUA which allows for such operation. TOP OF CEMENT OF 1ST STRING/PRODUCTION CASING WILL BE >500 FEET ABOVE TOP OF GAS.

34. Location ID: 336038

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Shauna Redican

Title: Permit Representative Date: 6/1/2012 Email: sredican@anteroresources.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 6/29/2012

API NUMBER

05 045 17570 00

Permit Number: _____ Expiration Date: 6/28/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY IS REQUIRED. (PROCEDURES AND SUBMITTAL REQUIREMENTS FOR COMPLIANCE WITH COGCC ORDERS NOS. 1-107, 139-56, 191-22, AND 369-2 (JULY 8, 2010)). SEE ATTACHED NOTICE.

(5) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

(6) OPERATOR MUST ENSURE 110 PERCENT SECONDARY CONTAINMENT FOR ANY VOLUME OF FLUIDS CONTAINED AT WELL-SITE DURING DRILLING AND COMPLETION OPERATIONS. IF FLUIDS ARE CONVEYED VIA PIPELINE, OPERATOR MUST IMPLEMENT BEST-MANAGEMENT-PRACTICES TO CONTAIN ANY UNINTENTIONAL RELEASE OF FLUIDS.

(7) FLOWBACK TO TANKS ONLY. SUBMIT A SECONDARY AND TERTIARY CONTAINMENT PLAN VIA SUNDRY NOTICE FORM 4 FOR THE TANKS. SUBMIT VIA EMAIL TO ATTN: LINDA SPRY-O'ROURKE. OBTAIN APPROVAL OF THE PLAN PRIOR TO FLOWBACK.

(8) NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT. THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT.

(9) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 135 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400284817	FORM 2 SUBMITTED
400287146	30 DAY NOTICE LETTER

Total Attach: 2 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Changed qtr/qtr to Lot 7. Location built; no 2A submitted and all five conditions met. No LGD or public comments. Final Review--passed.	6/26/2012 1:55:47 PM
LGD	Passed DB	3/5/2012 3:45:36 PM

Total: 2 comment(s)

BMP

Type

Comment

--	--

Total: 0 comment(s)